

North Hertfordshire Local Plan

Note to Inspector – Examination Document 109

Matter 1 – Missing correspondence regarding engagement between NHDC and HCC in relation to education matters

Contents:

Appendix No.	Date	Summary of Communication
1.	August 2013	HCC response to NHDC Housing Additional Locations Options 2011 - 2031
2.	August 2013 to January 2014	Email exchanges between NHDC and HCC re. education provision
3.	5 November 2014	HCC email to NHDC with document setting out primary and secondary education requirements
4.	8 December 2014 to 11 December 2014	Email exchange between NHDC and HCC
5.	10 July 2015	HCC letter to NHDC regarding all-through school provision
6.	19 August 2015	HCC email to NHDC with Stevenage Secondary Education Need Paper to NHDC
7.	20 August 2015	NHDC email to HCC re. education need paper
8.	8 September 2015	HCC email to NHDC re. education need paper
9.	February to March 2016	Email correspondence between HCC and NHDC
10.	18 April 2016	NHDC email to HCC
11.	12 May 2016	HCC letter to NHDC
12.	24 May 2016	Meeting between NHDC and HCC
13.	17 July 2016 to 22 July 2016	Email exchange between HCC and NHDC
14.	23 January 2017	NHDC email to HCC
15.	2 February 2017	Meeting between HCC and NHDC re. education provision
16.	9 March 2017	Meeting between HCC and NHDC re. education provision
17.	23 March 2017	HCC email to NHDC re. alternative school site
18.	12 April 2017	HCC sends two transport assessments to NHDC

Appendix 1

HCC response to NHDC Housing Additional Locations Options 2011 – 2031

August 2013

By e-mail

Hertfordshire County Council
County Hall
Hertford SG13 8DE

Tel: 01992 588275
Email: ailsa.davis@hertsc.gov.uk
Contact: Ailsa Davis

Date August 2013

Dear Ms Skeels

NORTH HERTFORDSHIRE DISTRICT COUNCIL LOCAL PLAN – HOUSING ADDITIONAL LOCATION OPTIONS

Thank you for your email sent 2 July 2013 consulting Hertfordshire County Council on the additional/amended housing sites put forward under the previous consultation on growth levels and directions in March 2013.

This response is made by Hertfordshire Property on behalf of Children's Services, Health and Community Services, Early Years and Childcare, Youth, Libraries, Fire and Rescue Services, Gypsy Section and also on behalf of the Waste Disposal Authority.

We continue to positively welcome the ongoing opportunity being provided to engage in discussions with the Local Planning Authority (LPA) to identify the implications, where possible, for the services and service delivery. In this response we have sought to identify how the proposed housing growth level and location of new housing within North Hertfordshire could impact upon service requirements and the need for additional sites from a spatial planning perspective.

When undertaking high level school place planning related to new residential development (e.g. at Local Planning stage), a ratio of 1FE (210 pupils) per 500 dwellings is applied based on a study of 49 Hertfordshire developments undertaken by Hertfordshire County Council's (HCC) demographer (c 2008). This work produced a yield range of 1FE per 500 dwellings (42 children per 100 dwellings/97.5% confidence of not underestimating child yield) to 1FE per 850 dwellings (24.7 children per 100 dwellings/50% confidence of not underestimating child yield). The County Council applies the upper end of the range, 1FE/500 dwellings, in the first instance, for reasons of prudence.

These representations should be read in conjunction with the HCC representations dated March 2013 submitted in response to your previous Local Plan consultation regarding housing growth levels and directions.

I will now deal with each settlement where additional or amended sites have been put forward setting out HCC's infrastructure requirements:

North East Stevenage

Reduced scale of development

Sites 226 and 227 = 925 dwellings (approx)

1FE to 1.8FE

Infrastructure Requirements:

- 1 new primary school
- New secondary school at Great Ashby – site of secondary school granted planning permission April 2010 should be designated as an education zone/allocation within the Local Plan to provide flexibility and ensure sufficient land is available to meet educational need
- Nursery provision for up to 46 to 78 children
- Improvements to existing Great Ashby Children's Centre
- Bowes Lion House Youth Centre in central Stevenage upgraded and extension to existing Great Ashby community centre to accommodate youth provision
- New and enlarged library as part of shared service development within town centre

Stevenage Borough Council are also proposing housing within their boundary to the north of the settlement. Any strategic housing site that spans both North Herts and Stevenage should be treated in a holistic manner in terms of infrastructure provision.

Hitchin

SW Hitchin strategic site – Reduced scale of development

Site 209 = 2,880 dwellings (approx)

3.4FE to 5.8FE

Infrastructure Requirements:

- 3 new primary schools;
- 1 new secondary school (current limited capacity in Hitchin secondary schools required to meet existing forecast need);
- Nursery provision for up to 142 to 242 children;
- Children's centre;
- Youth provision within new community centre;
- Improvements to Hitchin library;
- Hitchin fire station would need to become a wholetime 24 hour crewed fire station. This means it will be necessary to increase the number of firefighters from the existing 14 to 28 personnel.

East and NE of Luton

Sites 212A, 212B and 212C = 2000 dwellings (approx)

2.4FE to 4FE (Hertfordshire County Council child yield rate of 1FE per 850 to 500 dwellings)

6.5FE (Luton Borough Council child yield rate of 1FE per 305 dwellings)

In addition to;

Up to 1,400 dwellings

1.6FE to 2.8FE (Hertfordshire County Council child yield rate of 1FE per 850 to 500 dwellings)

4FE (Luton Borough Council child yield rate of 1FE per 305 dwellings)

Total = 4FE to 6.8FE (Herts yield) or 10.5FE (Luton yield)

Infrastructure Requirements:

- It would be prudent to seek 10.5FE worth of school provision, as the population profile on the edge of Luton is likely to reflect the existing population demographic of Luton. Following discussions with Luton BC, HCC would request either 5 x 2FE primary schools and a 10FE secondary school or a mixture of all through provision. Existing Hitchin secondary schools have no capacity to accommodate the growth from this site and there is no obvious current capacity at a secondary level that relates well to the east of Luton development elsewhere in Hertfordshire. Luton BC have also confirmed to HCC that a solution for secondary cannot rely on Luton for additional capacity, therefore the development would have to meet its own infrastructure needs.
- Nursery provision for 168 to 286 children;
- New Children's Centre
- Youth provision within new community centre
- Improvements to existing Library or mobile library service (TBC with Luton Borough Council)

Knebworth

Site 211 = 58 dwellings (approx)

0.06FE to 0.1FE

In addition to;

Non-strategic sites (priority 1,2 and 3) – Up to 979 dwellings

1.1FE to 2FE

Infrastructure Requirements:

- New primary school
- Nursery provision for up to 52 to 88 children
- No capacity in existing central and southern Stevenage secondary schools. Ideally pupils would travel to new secondary in West of Stevenage if that site were to come forward or should one of the northern Stevenage strategic sites come forward, pupils

in Stevenage could be redistributed to the new secondary school in the north to free up capacity in the centre and south of the town.

- Youth facility within a new or extended community hall
- No additional Children's Centre provision, continue to use Barleyfields.

Wymondley

Sites 229, 230 and 231 = 402 dwellings (approx)

0.5FE to 0.8FE

In addition to;

Site 232 (Amended site 122) – Reduced scale of development = 300 dwellings (approx)

0.4FE to 0.6FE

Total = 0.9FE to 1.4FE

Infrastructure Requirements:

- Existing village school does not have expansion potential unless additional land is acquired to increase the site area or detached playing fields are identified. School could be relocated onto a new 2FE site.
- As there is no capacity in existing Hitchin secondary schools to accommodate this housing, Wymondley expansion can only go ahead if South West Hitchin expansion goes ahead as pupils from Wymondley would go to the new Hitchin secondary schools.
- Nursery provision for 35 to 59 children.

Baldock

Sites 200, 201 and 202 = 3,694 dwellings (approx)

4.4FE to 7.4FE

In addition to;

Non-strategic sites (priority 1, 2 and 3) = Up to 1177 dwellings

1.3FE to 2.3FE

Total = 5.7FE to 9.7FE

Infrastructure Requirements:

- Five new primary schools
- Nursery provision for up to 241 to 410 children
- New secondary school
- New Children's Centre
- Youth provision within new community centre
- Improvements to existing Library or mobile library service

Barkway

Site 203 = 40 dwellings (approx)

0.08FE

In addition to;

Non-strategic sites (priority 1, 2 and 3) = Up to 155 dwellings

0.3FE

No infrastructure requirements

Barley

Site 204 (enlarged site 27) = 61 dwellings (approx)

0.1FE

No infrastructure requirements

Codicote

Sites 205, 206 and 207 = 169 dwellings (approx)

0.3FE

In addition to;

Non-strategic sites (priority 1, 2 and 3) = Up to 134 dwellings

0.3FE

Infrastructure requirements:

- Additional school places required. To be provided by expansion of existing primary school, subject to planning permission.

Graveley

Site 208 = 8 dwellings (approx)

0.01FE

In addition to;

Non-strategic sites (priority 1, 2 and 3) = Up to 88 dwellings

0.2FE

No infrastructure requirements

Offley

Site 213 = 9 dwellings (approx)

0.01FE

In addition to;

Non-strategic sites (priority 1, 2 and 3) = Up to 62 dwellings

0.1FE

No infrastructure requirements

Pirton

Site 214 = 47 dwellings (approx)

0.09FE

In addition to;

Non-strategic sites (priority 1, 2 and 3) = Up to 146 dwellings

0.3FE

No infrastructure requirements

Preston

Site 215 and 216 = 64 dwellings (approx)

0.1FE

No infrastructure requirements

Royston

Site 217 and 218 = 353 dwellings (approx)

0.7FE

In addition to;

Non-strategic sites (priority 1, 2 and 3) = Up to 877 dwellings

1.7FE

No infrastructure requirements

St Ippolyts

Sites 219, 220, 221, 222, 223, 224, 225 = 520 dwellings (approx)

1FE

In addition to;

Non-strategic sites (priority 1, 2 and 3) = Up to 42 dwellings

0.08FE

Infrastructure requirements:

- St Ippolyts CofE primary school site is small and would be difficult to expand due to town planning constraints. The child yield from the additional housing sites could not be accommodated by the existing primary school. The yield could be accommodated by relocating the existing school onto a new 2FE school site. Alternatively, it could be accommodated by the new primary schools in the SW Hitchin expansion. Therefore, if

the existing school is not relocated onto a new 2FE site, these additional sites should not be considered unless the SW Hitchin expansion goes ahead.

- HCC wish to object to the loss of the detached playing field for St Ippolyts CofE Primary school (site 223 Folly Lane). There are no other suitable or available sites that could be used as a replacement. The loss of the school playing field and lack of a suitable/available alternative would have a detrimental impact on the quality of education delivered at this school.

Weston

Site 228 = 25 dwellings (approx)

0.05FE

No infrastructure requirements

Yours sincerely

Ailsa Davis
Senior Planning Officer
Hertfordshire Property

Appendix 2

Email exchanges between NHDC and HCC re education
provision

August 2013 – January 2014

From: Karen Allen
Sent: 14 August 2013 01:01
To: Jacqueline Nixon; Alexandra Stevens
Cc: Chris Carter; Louise Symes; Simon Ellis; Richard Kelly
Subject: CIL meeting on the 5th September CIL (Part 1) and Education (Part 2)

To Jacqueline,

Thank you for the CIL letter dated 30th July 2013, the County Council's perspective on this is very useful. We look forward to meeting with you at our offices on the 5th September. I understand Simon Ellis has arranged this with you.

We think it would also be very useful if we could also talk to you about education provision as Part 2 of the same meeting. In particular capacity of schools within the villages and could the new dwellings be accommodated?

Our members have asked us to look at the possibility of spreading out some of the growth within the villages as well as having some strategic sites. I attach a spreadsheet which shows possible dwelling numbers. This includes a comparison of what figures we had for the January 2013 IDP which might be useful. A number of villages remain unchanged. However, the yellow shows where the most changes could be within the villages. I have also shown some of the changes within the towns too, but I think we can just add this to the FE requirements we already know.

If there is no way of increasing capacity within a particular village, rather than discounting it, we would like to explore the alternative of looking at nearby schools capacity or increasing the capacity to accommodate growth in another village and/or other alternatives. The grouping of smaller settlements, whereby developments in one village support services in another nearby, is referred to in Paragraph 55 of the NPPF.

We have a member meeting on the 4th September, whilst I appreciate that our meeting will be the day after, it would be useful if you could give us some initial feedback before the meeting so that we can discuss the issues with our members and feedback any issues with you the following day. I would be grateful if you could therefore provide an initial response to the spreadsheet by **Friday 30th August**.

Please note that the dwelling numbers are just for discussion purposes and have not been agreed in any way by our members.

Thanks for your continued help. Should you wish to have a chat on the telephone, let me know and I can arrange a suitable time.

Karen Allen
Senior Planning Officer

Direct Dial: 01462 474562

North Hertfordshire District Council
Council Offices
Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF
karen.allen@north-herts.gov.uk
www.north-herts.gov.uk

Committee Area	A: Civil parish	F: Households at 2011	Completions 2011-2012	Completions 2012-2013	Permissions likely to happen at 1 Apr 2013	Small sites estimate	Possible dwellings (Greens)	Possibles + small + pp + comp	Growth	Jan 13 IDP figures including small +pp+ comp	
Baldock	Ashwell	802	3	1	12	6	53	75	9%	32	
Baldock	Baldock	4491	24	22	52	32	1219	1349	30%	1173	
Baldock	Bygrave	99	0	0	0	1	0	1	1%	0	
Baldock	Caldecote	8	0	0	0	0	0	0	1%	0	
Baldock	Clothall	64	0	0	0	0	0	0	1%	0	
Baldock	Hinxworth	129	2	0	0	1	0	3	2%	2	
Baldock	Newnham	43	0	0	0	0	0	0	1%	0	
Baldock	Radwell	41	4	0	4	0	0	8	20%	8	
Baldock	Rushden	97	0	0	1	1	0	2	2%	0	
Baldock	Sandon	208	0	0	9	1	0	10	5%	8	
Baldock	Wallington	51	0	0	0	0	0	0	1%	0	
Baldock	Weston	427	0	-1	2	3	25	29	7%	0	
Hitchin	Hitchin	14865	101	26	216	105	850	1298	9%	927	
Hitchin	St Ippolyts	767	2	0	12	5	194	213	28%	31	* Note 67 dw would be Land North of Pound farm and may r
Letchworth	Letchworth	14533	171	104	38	103	520	936	6%	1071	
Royston	Barkway	323	0	10	8	2	188	208	64%	51	Assuming that this could be accommodated by the reserved
Royston	Barley	279	0	0	4	2	7	13	5%	8	
Royston	Kelshall	64	0	1	0	0	0	1	2%	1	
Royston	Nuthampstead	56	0	0	0	0	0	0	1%	0	
Royston	Reed	136	0	0	0	1	31	32	24%	41	
Royston	Royston	6784	61	122	199	48	680	1110	16%	915	Assuming that existing capacity would still accommodate thi
Royston	Therfield	214	3	0	0	2	17	22	10%	3	
Southern	Codicote	1418	2	0	19	10	171	202	14%	53	Can the school be extended?
Southern	Graveley	212	0	2	1	2	8	13	6%	6	
Southern	Great Ashby	2179	0	0	0	15	0	15	1%	0	
Southern	Hexton	52	0	0	1	0	0	1	3%	0	
Southern	Holwell	159	-2	0	11	1	0	10	6%	4	
Southern	Ickleford	828	0	0	1	6	9	16	2%	9	
Southern	Kimpton	865	3	-1	9	6	107	124	14%	79	
Southern	King's Walden	399	1	1	-1	3	16	20	5%	1	
Southern	Knebworth	1948	0	0	6	14	607	627	32%	10	A new school? Where could this be?
Southern	Langley	74	0	0	1	1	0	2	2%	1	
Southern	Lilley	162	0	0	0	1	0	1	1%	0	
Southern	Offley	588	3	0	8	4	62	77	13%	70	
Southern	Pirton	502	0	1	5	4	120	130	26%	2	Can the school be extended?
Southern	Preston	152	0	0	10	1	25	36	24%	10	
Southern	St Paul's Walden	521	0	2	3	4	44	53	10%	44	
Southern	Wymondley	470	6	1	4	3	300	314	67%	7	HCC have said that the village school has limited expansion potential, unless additional land is acquired to increase the site area or detached playing fields are identified. Alternatively the school could be located to a new site. Secondary school provision needs
	TOTAL	55010	384	291	635	390	5253	6953 0.126395 5147	13%	4567	

From: Ailsa Davis [<mailto:Ailsa.Davis@hertfordshire.gov.uk>]
Sent: 29 August 2013 09:52
To: Karen Allen
Cc: Richard Kelly; Louise Symes; Chris Carter; Jacqueline Nixon; David Hill
Subject: RE: CIL meeting on the 5th September CIL (Part 1) and Education (Part 2)

Karen,

Yes, HCC would be looking to collect s106 for secondary but not primary in the rural areas where it has been identified there would be no infrastructure requirements as a result of the proposed housing. Royston can still accommodate the planned housing growth at middle and upper schools. However, should the forecast change, HCC would reserve the right to seek s106 contributions to expand a school where required.

Regards

Ailsa Davis
Senior Planner, Development Services
Estate and Asset Management
Postal Point CHO315
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DE
t: 01992 588275 Comnet / Internal: 28275

From: Karen Allen [<mailto:Karen.Allen@north-herts.gov.uk>]
Sent: 29 August 2013 09:42
To: Karen Allen; Ailsa Davis
Cc: Richard Kelly; Louise Symes; Chris Carter; Jacqueline Nixon; David Hill
Subject: RE: CIL meeting on the 5th September CIL (Part 1) and Education (Part 2)

Hi Ailsa,

I forgot to ask whether this also means that you will not be asking for s106 in relation to primary schools for those rural areas where no infrastructure issues are raised because there is capacity. I would be grateful if you could clarify please.

Thanks again

From: Karen Allen
Sent: 29 August 2013 08:46
To: 'Ailsa Davis'
Cc: Richard Kelly; Louise Symes; Chris Carter; Jacqueline Nixon; David Hill
Subject: RE: CIL meeting on the 5th September CIL (Part 1) and Education (Part 2)

To Ailsa,

Thanks for getting back to me quickly. The information you have provided is very useful and should hopefully help our members next week.

In relation to the rural areas where you say no infrastructure requirements, can you clarify whether you will be wanting to collect s106 contributions in relation to the secondary schools that would serve these developments? I would assume that the dwellings would add to the cumulative totals for each town? If so I am assuming Royston would still be able to accommodate growth as there is capacity at middle and upper schools.

Thanks again

Karen Allen
Senior Planning Officer

Direct Dial: 01462 474562

North Hertfordshire District Council
Council Offices
Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF
karen.allen@north-herts.gov.uk
www.north-herts.gov.uk

From: Ailsa Davis [<mailto:Ailsa.Davis@hertfordshire.gov.uk>]
Sent: 28 August 2013 13:52
To: Karen Allen
Cc: Richard Kelly; Louise Symes; Chris Carter; Jacqueline Nixon
Subject: CIL meeting on the 5th September CIL (Part 1) and Education (Part 2)

Hi Karen,

Thanks for clarifying this and I'm relieved you have my reps! Please find attached the HCC reps (services) relating to the March 2013 Housing Growth Level and Direction consultation and the July 2013 additional/amended sites consultation. As discussed, these are based on the strategic sites and priority 1,2 and 3 sites that NHDC have most recently consulted on and include information on the villages.

I have checked the totals you have sent through against these responses and am satisfied that what I have said in relation to the majority of villages is still relevant. In addition I have the following comments:

St Ippolyts

I would draw your attention to the July 2013 reps in relation to housing at St Ippolyts. This related to a housing figure of approx 562. Your spreadsheet suggests a figure of 213 (67 of which may relate more to Hitchin Schools), leaving potentially 146 at St Ippolyts. St Ippolyts Primary is currently full and the forecast is showing that it will remain at capacity going forwards. Therefore, as stated in the July 2013 reps, the school site is small and would be difficult to expand due to town planning constraints. The child yield from the 146 houses could not be accommodated by the existing primary school. The yield could be accommodated by relocating the existing school onto a new 2FE school site. Alternatively, it could be accommodated by the new primary schools in the SW Hitchin expansion. Therefore, if the existing school is not relocated onto a new 2FE site, this level of housing should not be considered unless the SW Hitchin expansion goes ahead.

Codicote

As per my reps - primary school would need to be expanded and there is expansion potential from a town planning perspective. Your figure of 202 could be accommodated with expansion of the school.

Knebworth

New primary school required as per previous reps. HCC owns a site at Watton Road (currently a recreation ground). Not sure whether it is in right location, as close to existing school.

Pirton

As per my reps - school can accommodate small amount of expansion (Conservation Area).

Hope the attached and above info is useful.

Regards

Ailsa Davis
Senior Planner, Development Services
Estate and Asset Management
Postal Point CHO315
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DE
t: 01992 588275 **Comnet / Internal:** 28275

From: Karen Allen [<mailto:Karen.Allen@north-herts.gov.uk>]
Sent: 28 August 2013 10:32
To: Ailsa Davis
Cc: Richard Kelly; Louise Symes; Chris Carter
Subject: RE: CIL meeting on the 5th September CIL (Part 1) and Education (Part 2)

Thanks for the quick chat on the telephone. We have got your letter, which has been split up into the different areas for our analysis, hence the reason why I hadn't realised. My apologies.

It might be quicker if you sent me the original letters directly to me as my colleagues are all in a meeting at the moment.

With regards to the January 2013 IDP figures they are different to our consultation responses on the Housing Options. These were based on priority 1 and 2 sites only and form part of an evidence base to the CIL. I had been liaising with yourself, Alex and Jacqueline during 2012 in relation your requirements. Since your responses are not in relation to this I don't think you need to do a further comparison in relation to the IDP. I just included it to be of assistance more than anything else.

I would say that the latest spreadsheet I sent you doesn't necessarily represent all priority 1,2 and 3 sites + additional sites you have previously responded to. They may be a combination of just some but possibly not all. You might therefore want to check the totals I sent through against your previous responses.

Having had a quick look I can see you don't have a problem with Weston and we can deal with this one easily. However, Codicote you refer to 134 and 169 dwellings and that the school could be expanded. The figure we are now looking at is 202 which is a different number to the previous consultations. Can it still be expanded meet this? I will have a look at the rest when I get your response.

I hope this clarifies things a bit better.

Thanks
Karen Allen
Senior Planning Officer

Direct Dial: 01462 474562

North Hertfordshire District Council
Council Offices
Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF
karen.allen@north-herts.gov.uk
www.north-herts.gov.uk

From: Ailsa Davis [mailto:Ailsa.Davis@hertfordshire.gov.uk]
Sent: 25 September 2013 17:05
To: Richard Kelly
Cc: Alexandra Stevens; Karen Allen; Jacqueline Nixon; Matthew Wood
Subject: Codicote

Richard,

We are not suggesting that you cannot provide 200 houses in Codicote. As advised previously, the way to enable the housing to come forward is to allocate a school site of sufficient size to relocate and expand the existing school. Childrens' Services have advised:

"As long as the site allocation is sufficient to accommodate a 2fe school, how we actually deliver this can be determined by us at a later date".

The existing school site could be redeveloped for housing as you suggest, enabling you to provide more houses in the village.

Regards

Ailsa Davis
Senior Planner, Development Services
Estate and Asset Management
Postal Point CHO315
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DE
t: 01992 588275 **Comnet / Internal:** 28275

From: Richard Kelly [mailto:Richard.Kelly@north-herts.gov.uk]
Sent: 25 September 2013 15:19
To: Ailsa Davis
Cc: Alexandra Stevens; Karen Allen
Subject: RE: Codicote

Hello Ailsa

Thank you for doing that extra work. As I'm sure you'll appreciate I was hoping it would yield a more constructive answer, but there we go. We don't have enough potential sites at Codicote to deliver 500 extra homes, so the idea of doing two forms of entry doesn't really work unless you are pulling in more children from outside the village.

I think the school (or rather the head) did comment on the consultation documents, but we haven't had any discussions with them about emerging thoughts. For the moment I'd hold fire on approaching them (or Diocese). I have a meeting on Friday with Cllr Brindley, our planning portfolio holder, who happens to also be the member for Codicote. We then have an informal session of our Local Plan Working Party on Monday. After those meetings I'll feed back their reactions to the possibility of not being able to allocate any sites in Codicote. We can then consider if there is a need to take discussions further.

Thanks

Richard Kelly
Principal Strategic Planning Officer

Direct dial: 01462 474847

North Hertfordshire District Council
Council Offices

Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

richard.kelly@north-herts.gov.uk
www.north-herts.gov.uk

From: Ailsa Davis [<mailto:Ailsa.Davis@hertfordshire.gov.uk>]
Sent: 25 September 2013 14:45
To: Richard Kelly
Cc: Alexandra Stevens; Karen Allen
Subject: Codicote

Richard,

I have gone back to Childrens' Services to see if there is a way round this and the position appears to be as follows:

As stressed previously Codicote Primary is currently full in all years (oversubscribed in some) and our forecast suggests there is already more demand than there are places. Current Childrens' Services strategy is that the neighbouring primary planning area (Welwyn) will cater for the additional demand from Codicote. However, the next nearest school - Welwyn St Mary's - is full, oversubscribed and its own Admitting Authority are very keen to provide its places to 'local' families (i.e. from Welwyn). The other schools in the planning area are further away and HCC would not necessarily expect primary aged children to travel to them from Codicote unless by choice. Furthermore, all but one are at capacity currently and we also anticipate that any surplus capacity would be used to help out the Knebworth area deficit in places.

Childrens' Services have previously looked at Codicote in terms of where its children actually live and the vast majority live in Codicote - see attached dotted map. Therefore our position remains that Codicote as a village 'swallows its own smoke' - i.e. it is self-sufficient with the school serving its primary demand. You will see that there are already children living in Langley and Old Knebworth attending the school. The majority of families living in Knebworth choose Knebworth Primary as first preference and so are unlikely to choose Codicote.

200 homes therefore is not ideal as there is nowhere for the additional children to go without having to travel, and the pupil yield is not enough to warrant a new school. Our ideal position would be for NHDC to increase the housing numbers in Codicote to a size which will yield 1FE i.e. 500, ensuring that a school site is provided within this. If not, then the only way around this as far as I can see is that NHDC allocates a school site of sufficient size to relocate and expand the existing school as you suggest below.

The other point I need to raise is whether the school is aware of the situation? If not, Childrens' Services need to make them aware sooner rather than later and before NHDC set anything in stone - as a church school we will also need to let the Diocese know. Childrens' Services are happy to go out to see them, but will need further information around what NHDC are doing and when.

Regards

Ailsa Davis
Senior Planner, Development Services
Estate and Asset Management
Postal Point CHO315
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DE
t: 01992 588275 Comnet / Internal: 28275

From: Richard Kelly [<mailto:Richard.Kelly@north-herts.gov.uk>]
Sent: 19 September 2013 09:01
To: Ailsa Davis
Cc: Alexandra Stevens; Karen Allen
Subject: RE: Little Wymondley and Codicote

Hello Ailsa

Thanks for that information, which is useful. I think we need to explore possibilities for Codicote further. The level of demand for housing is such that I can't lightly write off 200 homes at one of our best served villages in terms of the facilities it has. This would also give me a headache in finding alternative sites for those 200 homes. If the problem is with the current site, what if we were to move the school to a new 2FE site (part of our housing site 29 at the southern end of High Street might work) and redevelop the current school site for housing? How does Codicote's catchment relate to nearby school-less villages, notably Langley and Old Knebworth - could we divert children from those villages to Codicote to make 2FE work - and presumably thereby reduce pressure on St Ippolyts and Knebworth schools, which you've said are both close to capacity? How does Codicote relate to Welwyn village's schools? If there are surpluses in Welwyn, could some Codicote kids go there? Or if there's pressure on places in Welwyn could the surplus come out to Codicote?

Sorry to bombard you with questions, but I think we need to be a bit more proactive about trying to find a solution for this village.

Happy to discuss.

Regards

Richard Kelly
Principal Strategic Planning Officer

Direct dial: 01462 474847

North Hertfordshire District Council
Council Offices
Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

richard.kelly@north-herts.gov.uk
www.north-herts.gov.uk

From: Ailsa Davis [<mailto:Ailsa.Davis@hertfordshire.gov.uk>]
Sent: 18 September 2013 11:34
To: Richard Kelly
Cc: Alexandra Stevens
Subject: Little Wymondley and Codicote

Richard,

Following our meeting on the 5 September, I have carried out site visits to the schools at Little Wymondley and Codicote and have discussed the planned housing numbers with Childrens' Services.

Little Wymondley

CS have confirmed an expansion to 1FE would satisfy forecast demand and also the yield from the 300 houses. Following my site visit, I consider that the school could accommodate a 0.5FE expansion from a

town planning and highway perspective, however a formal highway assessment has not been commissioned.

Codicote

CS have confirmed that the forecast shows that the school is full with some unsatisfied demand. Expanding the school by 0.4FE to accommodate the yield from the 200 houses is not ideal to CS, who prefer expansions to bring schools up to 1, 2 or 3FE. Having visited the site and seen the highway network around the school, I do not believe the school is capable of a 1FE expansion. However, a formal highway assessment has not been commissioned. Given the concerns over town planning and highways and the fact CS would not want to expand this school to 1.4FE (awkward size) or 2FE (too much capacity), I do not feel that the settlement could accommodate 200 houses from a primary education perspective.

Happy to talk through further if you want.

Regards

Ailsa Davis
Senior Planner, Development Services
Estate and Asset Management
Postal Point CHO315
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DE
t: 01992 588275 Comnet / Internal: 28275

From: Richard Kelly [<mailto:Richard.Kelly@north-herts.gov.uk>]
Sent: 10 September 2013 15:46
To: Alexandra Stevens; Ailsa Davis
Subject: Little Wymondley

Hello Alex and Ailsa

Just to let you know, we had a meeting last week with the promoters of land at Little Wymondley, Richard Daniels of New Road Ltd and his consultant Neil Osborn of DLP. We did discuss the schooling situation, and they probably will be in touch with you (if they haven't already) about options for expanding the school to a full 1FE and how much leeway you'd like. We've said that probably those are for you and them to discuss in the first instance, as it'll probably be about costs etc to begin with. That said, if you think it would be useful for us to join in the conversation, just let us know.

Thanks


Richard Kelly
Principal Strategic Planning Officer

Direct dial: 01462 474847


North Hertfordshire District Council
Council Offices
Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

richard.kelly@north-herts.gov.uk
www.north-herts.gov.uk

Home location of pupils attending Codicote C of E Primary VAC (54) - close up (School Census Jan. 2011)



- Primary planning areas
- Primary schools
- Pupils at Codicote Primary



Produced using ArcView by
Hertfordshire County Council
CSF Department
29 February 2012



From: Ailsa Davis [mailto:Ailsa.Davis@hertfordshire.gov.uk]
Sent: 30 October 2013 16:34
To: Karen Allen
Subject: Update to IDP

Karen,

Please see the attached document which was produced in relation to a request for more up to date costing advice 1 Form Entry + Nursery And 2 Form Entry + Nursery, New Build Primary School in Hertfordshire. The work was produced by a quantity surveyor.

This new work identifies that the estimated cost of:

- a new 1 fe primary school would be in the range of £4.2 - £4.95 million and
- the cost of a new 2 fe primary school would be in the range of £7 to £8 million

In addition, there was recently an education and skills cabinet paper which sought to begin to prioritise secondary expansions.

<http://www.hertsdirect.org/mm/17912228/17912237/enteduskillitem320130920.doc>

In that, you will note that the issue of cost was one that the report is unable to be too precise about. However, at 8.1 of the report attributes an aggregate cost to the schemes, and divided across the five schemes identified, the aggregate cost is 2.87 million pounds. Therefore, our view is that it would be reasonable to attribute an estimated cost of;

£3 million to expand a secondary school by 1 form of entry.

Jacqueline has also asked colleagues in Building's Management to commission further work to consider the potential cost of ;

3fe primary school
5fe secondary school

and an all through 5 fe secondary/2 fe primary.

When the results of that work are known we will of course feed it through to you, hopefully so it can form part of any subsequent update of the IDP.

I also attach an updated education chapter and appendix D which reflects the latest position.

Regards

Ailsa Davis
Senior Planner, Development Services
Estate and Asset Management
Postal Point CHO315
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DE
t: 01992 588275 **Comnet / Internal:** 28275

**Cost Appraisal for
1 Form Entry + Nursery
And
2 Form Entry + Nursery,
New Build Primary School in Hertfordshire**

June 2013

Introduction

With the market changes in the construction industry over recent years I was asked to support the Strategic Asset Management Team with early cost advice for the new build of a 1FE and 2FE primary school, based on Hertfordshire area standards (which are based on BB99).

This would assist in budget setting and be the basis for negotiation with a developer for their contribution under a Section 106 Agreement.

At this stage there has been no input from other design team members, such as an Architect, M&E or Structural Engineers.

There has also been no scheme or criteria put forward as being the current construction design brief for Hertfordshire when designing either a 1FE or 2FE primary school.

Construction Cost Trends

Changes in the construction market are monitored by the Building Cost Information Service via their Tender Price Index and Building Cost Index (see Appendix 1).

The past year has seen a see-sawing in the BCIS All-in Tender Price Index which in itself could be indicative of a bottoming out in the market with a slow increase forecast in the following years.

It is the BCIS Tender Price Index that I have used to rebase all the cost information to a base of, **2nd Quarter 2013**.

Gross Internal Floor Areas

A variety of areas have been quoted and used on projects and in previous estimates.

From discussions between the Strategic Asset Management Team and Children's Services it has been established that there is an HCC Accommodation Model for Primary schools covering each example of Form Entry from ½ FE to 3FE, used extensively to assess current levels of accommodation. See Appendix 2.

From this the gross internal floor area for a 1FE Primary school (including Nursery), as the basis for this report, has been agreed at 1,404 m² and for 2FE Primary school (including Nursery) at 2,338 m².

Source of Cost Data

Over the years, Hertfordshire have developed and built a variety of new primary schools, generally 2 Form Entry.

Having no specific design brief, I have taken the more recent of these (tendered and constructed in the last 5 years) and analysed the elemental building costs.

The basis of the net building cost is based on the range of construction projects listed in Appendix 3

I have also compared the result to a cost study carried out by colleagues in Essex which analysed projects built across the three Counties of Hertfordshire, Essex and Suffolk and where significantly half the projects were carried out through the Smarte East framework.

Using the building only construction costs I have included for Preliminaries, Overheads & Profit and rebased the data to the **2nd Quarter 2013** within Hertfordshire.

Other Sources

During the course of this exercise I have spoken with Steve Clyne , EfM consultants, concerning the Ridgeway project (North London) and his assertion that a 1FE primary school may be built at a cost of £2.89M.

Enlightening as his approach would seem it is based on a system build PCC solution, as I understand it from Steve, he is at the stage of having instructed the contractor of his fixed budget together with a list of the employers' requirements.

At this time there has been no communication back as to what the contractors' proposals are for building within the budget and so it is unknown as to the extent of any compromises being made in the specification and what the long term effects are of operating a school following such a build and as such has not been taken account of in this exercise.

Average Net Building Cost

From the schemes selected the **average** net building cost, rebased to **2nd Quarter 2013** has been calculated as £1,850/m² with the range being from £1,730 to £2,000/m².

This assumes, single storey construction on a level greenfield site and excludes; site specific abnormalities / constraints, site works, external drainage and services, planning constraints, professional fees, etc.

1FE Costing

For the Build up of the Order of Cost estimate, based on the **average** Net Building Cost;

1,404 m2 @ £1,850 =	£2,597,400
External Works (26%)	£ 675,300
Drainage (7%)	£ 181,800
External Services (4%)	£ 103,900

sub-total	£3,558,400
Contingencies (5%) (design development / unforeseen items)	£ 106,750

sub-total	£3,665,150
Total Construction Budget Say	£3,665,000

Fees and Surveys

Feasibility Fees	£ 50,000
Surveys	£ 35,000
Professional/Design Fees	£ 450,000
Bldg Regs/Planning	£ 35,000

Other

Loose Furniture & Equipment	£ 250,000
Signage	£ 5,000
Landscaping	£ 35,000

Total	£4,525,000

With the net building cost range established above of between £1,730 and £2,000 per m2, this would establish a range of pricing in the order of;

Range £4.20 - £4.95M

=====

For this early stage estimate a base cost price range is stated which excludes any allowance for risk or inflation.

This needs to be refined when applied to a specific site and cost checks take place as the design / elements become more detailed.

An elemental breakdown of the major elements for the median net building costs has been included in Appendix 4 for developing the cost plan as design for a specific project progresses.

External Works / Services – Has not been measured separately but is based on an average percentage addition to the main building works derived from the range of projects used.

Specific requirements may vary the allowances, particularly around;

- Hardplay
- Sports Pitch
- Car parking
- Access road / drop of area

Furniture & Equipment

Furniture and Equipment has 2 main components;

1. Fixed furniture and equipment, such as blinds, pinboards and cloakroom equipment – included in the building cost.
2. Loose furniture and equipment, such as tables, desks, chairs, etc. Allowed for as an additional lump sum based on an allowance per classroom, dining room, etc.

IT equipment has not been specifically allowed for in the furniture allowance.

An example of the individual allowances for loose furniture and equipment has kindly been provided by Graham Phillips, made against the accommodation list for a 1FE Primary this is reproduced in Appendix 6.

His build up comes to in excess of £200k and includes his caveats as to what may or may not be included in the building contract.

With the mix between fixed and loose furniture open to interpretation and the fixed furniture allowance included in the building cost based on an average across the named projects I have kept the lump sum for loose furniture as my original allowance of £250,000 (£400,000 for 2FE).

Contingency / Risk Allowance

Included above is a 5% contingency allowance intended to cover unforeseen items and risk associated with the design development such as changes in estimating data, third party risks, statutory requirements, procurement methodology and delays in tendering.

Not Specifically Included are;

Construction Risks - site conditions, ground conditions, existing services and delays by statutory undertakers.

Client Change Risks – scope of works/brief, quality, enhancements and time.

Client Other Risks - early handover, postponement, acceleration, availability of funds, liquidated damages, unconventional tender action and special contract arrangements.

Environmental / Sustainability Strategy

IT

Inflation Allowance – beyond 2nd Quarter 2013

When a specific site is known, some costings may need to be increased to allow for known problems or abnormal indicators.

2FE Costing

Based on the same criteria and cost information as the early stage 1FE build up, then a 2FE scheme Order of Cost estimate, based on the **average** Net Building Cost and the HCC accommodation model area would be;

2,338 m2 @ £1,850 =	£4,325,300
External Works (26%)	£1,124,600
Drainage (7%)	£ 302,800
External Services (4%)	£ 173,000

sub-total	£5,925,700
Contingencies (5%) (design development / unforeseen items)	£ 296,300

sub-total	£6,222,000

Total Construction Budget Say £6,250,000

Fees and Surveys

Feasibility Fees	£ 60,000
Surveys	£ 45,000
Professional/Design Fees	£ 760,000
Bldg Regs/Planning	£ 60,000

Other

Loose Furniture & Equipment	£ 400,000
Signage	£ 5,000
Landscaping	£ 60,000

Total £7,640,000

With the net building cost range established above of between £1,730 and £2,000 per m2, this would establish a range of pricing in the order of;

Range £7.00 - £8.00M

=====

As before the base cost price range excludes any allowance for risk or inflation and needs to be refined when applied to a specific site and cost checks take place as the design / elements become more detailed.

The same caveats apply regarding External Works / Services and Furniture & Equipment which have been pro-rated.

BCIS / Market Influences

The estimate base is the 2nd Quarter 2013 using the indices available at the time of producing the estimate.

I currently monitor the BCIS indices, monthly, for changes to; the Cost Indices, Tender Indices and Location Factors and as mentioned at the beginning of this report the past year has seen a see-sawing in the BCIS All-in Tender Price Index which could be indicative of a bottoming out in the market with a slow increase forecast in the following years.

With the fluctuations being experienced, the reasonable life of this estimate is towards the end of August and much depends on the monitoring of future published indices for significant trends or changes that affect the base estimate and inflation predictions.

In addition the BCIS have made revisions to the method by which they now calculate the factors in their Location Study where again it would be advisable to monitor the ongoing published location factors which may affect the costings.

The construction market belief that the downward trend in pricing has bottomed out this year, predicts a steady year on year increase of 3% for tender inflation. The expectation is that the 'real' cost of a project will increase when a programme is known and the estimate rebased to allow for tender inflation to the forecast dates for construction.

Conclusion

The basic average net building rate of £1,850 per m² is a fair assessment based on past Hertfordshire projects and stands up to comparison with the average construction costs being experienced in neighbouring counties for education projects.

In taking this forward, as an early stage Order of Cost Estimate, without any design team input as to an indicative specification / design intent for the building, services or environmental strategy, there are still many areas of uncertainty where allowances have been made that will change with the specific requirements of a project.

Hence in setting an initial budget for a 1FE + primary school it is recommended that the upper limit of £4,950,000 is used and for a 2FE + primary school the upper limit of £8M, to then be followed up with a risk assessment / allowance made for the specific site.


This will in turn need to be monitored against changes in indices, location factors and specific project requirements as a scheme progresses.

In particular, inflation will have a major influence on the final cost with the likelihood of the steady annual inflation increases predicted needing to be applied to the costings which, as stated in the report, are at the base of 2nd Quarter 2013.

Gary Burton MRICS

Appendix 1

Construction Market – Tender Prices and Building Costs (Annual Percentage Change)



Appendix 2

HCC ACCOMMODATION MODEL 28/07/2010

	1/2 FE Primary 106 Pupils			1 FE Primary 210 Pupils			1.5 FE Primary 316 Pupils			2 FE Primary 420 Pupils			2.5 FE Primary 526 Pupils			3 FE Primary 630 Pupils		
	Model			Model			Model			Model			Model			Model		
	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²
Class Bases	3	60	180	6	60	360	9	60	540	12	60	720	15	60	900	18	60	1080
Reception	1	32	32	1	63	63	2	63	126	2	63	126	3	63	189	3	63	189
Nursery	1	35	35	1	69	69	1	69	69	1	69	69	1	69	69	2	69	138
Food Bay	1	4	4	1	4	4	1	4	4	0	4	0	0	4	0	0	4	0
Food/Des/Tech/Sci	0	22	0	0	22	0	0	22	0	1	22	22	1	22	22	1	22	22
ICT	1	19	19	1	37	37	1	37	37	2	37	74	2	37	74	2	37	74
SEN Resource Base	1	8	8	1	16	16	1	16	16	1	16	16	2	16	32	2	16	32
Total Basic Teaching Area	8	278		11	648		16	792		19	1027		24	1288		28	1656	
Small Group Rooms	1	12	12	3	12	36	4	12	48	5	12	60	6	12	72	7	12	84
Library	1	12	12	1	24	24	1	28	28	1	34	34	1	46	46	1	53	53
Total Learning Resources	2	24		4	60		6	78		8	94		7	118		8	137	
Small Hall	0	80	0	0	80	0	0	80	0	0	80	0	0	80	0	1	80	80
Activity Studio	0	45	0	0	45	0	1	45	45	1	45	45	1	45	45	1	45	45
Main Hall	1	165	165	1	165	165	1	165	165	1	185	185	1	185	185	1	185	185
Total Halls	1	166		1	166		2	210		2	230		2	230		3	310	
TOTAL TEACHING AREAS	11	487		16	774		22	1078		27	1361		33	1834		38	1882	
	Model 0.5FE			Model 1FE			Model 1.5FE			Model 2FE			Model 2.5FE			Model 3FE		
	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²
SENCo Base	0	8	0	0	8	0	0	8	0	1	8	8	1	8	8	1	8	8
Secure Reception	1	4	4	1	4	4	1	4	4	1	4	4	1	4	4	1	4	4
Admin & Secure Storage	1	5	5	1	10	10	1	12	12	1	14	14	1	16	16	1	18	18
Interview Room	1	8	8	1	8	8	1	8	8	1	8	8	1	8	8	1	8	8
Headteacher	1	10	10	1	10	10	1	10	10	1	12	12	1	12	12	1	15	15
Deputy Head	0	8	0	0	8	0	0	8	0	1	8	8	1	8	8	1	8	8
Reprographics	1	4	4	1	4	4	1	6	6	1	8	8	1	8	8	1	12	12
Sick Bay	1	3	3	1	3	3	1	3	3	1	3	3	1	3	3	1	3	3
Mt/Visiting Professionals	1	12	12	1	12	12	1	12	12	1	12	12	1	12	12	1	12	12
Staffroom Social & Work	1	16	16	1	31	31	1	41	41	1	51	51	1	61	61	1	71	71
ICT Tech/Server	1	5	5	1	5	5	1	5	5	1	5	5	1	5	5	1	5	5
Caretaker's Office	1	8	8	1	8	8	1	8	8	1	8	8	1	8	8	1	8	8
TOTAL STAFF AND ADMIN	10	76		10	96		10	108		12	141		12	163		12	172	
Teaching Storage	1	19	19	1	37	37	1	51	51	1	62	62	1	81	81	1	94	94
Other Storage	1	18	18	1	36	36	1	51	51	1	64	64	1	82	82	1	90	90
TOTAL STORAGE	2	37		2	73		2	102		2	128		2	183		2	184	
TOTAL NON TEACHING AREAS	12	112		12	188		12	211		14	287		14	318		14	368	
	Model 0.5FE			Model 1FE			Model 1.5FE			Model 2FE			Model 2.5FE			Model 3FE		
	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²
Dining Area	1	36	36	1	72	72	1	84	84	1	88	88	1	91	91	1	96	96
Kitchen/catering	1	15	15	1	30	30	1	35	35	1	45	45	1	55	55	1	66	66
Staff Toilets	1	6	6	1	12	12	1	12	12	1	12	12	1	14	14	1	16	16
Pupil Toilets	1	35	35	1	60	60	1	76	76	1	100	100	1	130	130	1	152	152
Disabled Toilets	1	7	7	1	7	7	1	7	7	1	7	7	1	7	7	1	14	14
Circulation 20% of Net Area	1	136	136	1	225	225	1	301	301	1	374	374	1	449	449	1	536	536
Plant 2% of Net Area	1	14	14	1	22	22	1	30	30	1	37	37	1	45	45	1	54	54
Partition 3% of Net Area	1	20	20	1	34	34	1	45	45	1	56	56	1	67	67	1	80	80
TOTAL NON NET AREAS	8	288.6		8	481.76		8	689.76		8	719.6		8	868.76		8	1014.6	
	Model 0.5FE			Model 1FE			Model 1.5FE			Model 2FE			Model 2.5FE			Model 3FE		
	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²	No	Size m ²	Total m ²
GRAND TOTAL	31	847.6		38	1493.8		42	1878.8		49	2307.6		66	2808.8		81	3362.6	
TOTAL NET AREAS	978			1123			1608			1870			2247			2882		

Appendix 3

Costings based on following past projects;

Project	Cost Base Date
Bushey Highwood	3 rd Quarter 2011
New Briars Primary School, Hatfield	4 th Quarter 2011
Watford Holywell	4 th Quarter 2011

Reference to;

Suffolk, Puddlebrook 1FE School (BCIS Analysis)

Essex, Takeley Primary School

Appendix 4

Basic Elemental Breakdown of Average Estimated Building Cost

Basic elemental analysis for refining cost model to value engineer an individual project, example shown for 1FE primary.

HCC		1FE + Primary	
		BASE DATE	2Q 2013
		NUMBER of STOREYS	1
		NUMBER of PLACES	240
		G.F.A.	1,404
		Example	
9A1		1FE Average	
Code	Element	Inc prelims @	16.28%
		Cost/m2	Cost
1A1	Substructure	136	190,860
	Substructure Total	136	190,860
2A1	Frame PC Sum	86	120,829
2B1	Upper Floors	3	3,753
2C1	Roof Structure	148	207,352
2C4	Roof Coverings & Drainage	51	71,898
2C7	Roof Lights	37	52,442
2D1	Staircases	1	1,460
2E1	External Walls	157	220,221
2F1	Windows & External Doors	150	210,594
2F4	Windows	0	0
2F7	External Doors	0	0
2G1	Internal Walls & Partitions	109	152,377
2G4	Glazed Screens	5	6,717
2G7	W.C. Cubicles	6	8,735
2H1	Internal Doors	74	104,012
	Superstructure Total	826	1,160,390
3A1	Wall Finishes	28	39,276
3B1	Floor Finishes	78	109,744
3C1	Ceiling Finishes	39	54,635
	Internal Finishes Total	145	203,655
4A1	Fittings, Fixtures & Furniture	131	184,313
	Fittings and Furnishings Total	131	184,313
5A1	Sanitary Appliances	25	34,422
5B1	Service Equipment	0	0
5C1	Disposal Installations (Int. Drainage)	5	6,808
5D1	Water Installations	0	0
5E1	Heat Source	0	0
5F1	Space Heating and Air Treatment	291	408,495
5G1	Ventilation Systems	0	0
5H1	Electrical Installations	248	348,427
5I1	Gas Installations	0	0
5J1	Lifts Installations	3	3,582
5K1	Protective Installations, inc Int. CCTV	17	23,632
5L1	Communications Installations	18	25,118
5M1	ICT Infrastructure Works	0	0
5N1	Specialist Installations	0	0
5N4	BWIC with Services	5	7,699
	Services Total	611	858,182
	TOTAL for BUILDING	1,850	2,597,400

Appendix 5

Location Factor

Since starting this exercise, the BCIS have changed the system they use for calculating the Location Indices, which stood at 12% above the National Average for Hertfordshire.

In June this year, their recalculation lowered this to 8% with no indication of the index they would standby for the months in between.

For the purpose of the benchmarking I have kept to the original factor of 12% and advise monitoring the position over the coming months together with the National Tender Index.

The full BCIS explanation is reproduced below;

BCIS Location Indices Updated

The BCIS Location Indices have been updated for the first time since July 2012.

13-Jun-2013

The BCIS systems used to calculate the Tender Price Studies were retired in August 2012, with the intention that they would be replaced soon after. However, around the same time, there were some concerns about the location indices, in particular the figures for Northern Ireland which were far lower than expected, and a project from the Scilly Isles which was causing the Islands' factor to increase significantly.

These anomalies warranted a review of the calculation method, as well as the transfer of the systems to the new platform. Unfortunately, it was not possible to complete this work within a reasonable period and a revised set of location indices were published on 13 June 2013, based on recalculated regional factors from projects between 2010 and 2012: the resulting regional factors being used to adjust previously published county and district factors.

The work to review and replace the BCIS Tender Price Studies is still in hand, but in due course, all of the studies will once again be updated on a regular basis.

Appendix 6

Furniture and Equipment

An example of the individual allowances made against the accommodation list for a 1FE Primary, provided by Graham Phillips, is reproduced below together with his caveats as to what may or may not be included in the building contract.

PROVISIONAL SCHEDULE OF FURNITURE & EQUIPMENT

1 FE PRIMARY SCHOOL

<u>ITEM DESCRIPTION/MODEL NO.</u>	<u>QTY</u>	<u>UNIT COST</u>	<u>EXT. COST</u>
<u>CLASSROOM FURNITURE</u>			
Nursery	1	£4,000.00	£4,000.00
Reception	1	£3,000.00	£3,000.00
Year 1	1	£3,000.00	£3,000.00
Year 2	1	£3,000.00	£3,000.00
Year 3	1	£3,000.00	£3,000.00
Year 4	1	£3,000.00	£3,000.00
Year 5	1	£3,000.00	£3,000.00
Year 6	1	£3,000.00	£3,000.00
<u>LEARNING RESOURCE AREA</u>			
Library Shelving	1	£8,000.00	£8,000.00
ICT Benching	1	£8,000.00	£8,000.00
Soft seating and tabling	1	£2,000.00	£2,000.00
<u>HALL</u>			
Fixed PE Equipment	1	£5,000.00	£5,000.00
Interactive Whiteboard or Data Projector & Screen	1	£5,000.00	£5,000.00
Sound System inc.pa System	1	£5,000.00	£5,000.00
Drama Lighting	1	£20,000.00	£20,000.00
Staging	1	£7,500.00	£7,500.00
Hall Chairs, linking (100)	1	£2,500.00	£2,500.00
<u>DINING AREA</u>			
Dining Furniture for 120 people	1	£8,000.00	£8,000.00
<u>FOOD TECHNOLOGY ROOM</u>			
White Goods (Cookers/Fridge/Freezer/Dishwasher/Microwave)	1	£2,500.00	£2,500.00
Furniture	1	£500.00	£500.00
<u>MAIN SCHOOL OFFICE</u>			
Furniture	1	£5,000.00	£5,000.00
<u>MEDICAL ROOM</u>			
Furniture	1	£500.00	£500.00
<u>HEAD'S OFFICE</u>			
Furniture	1	£3,500.00	£3,500.00
<u>STAFF ROOM</u>			
Furniture (includes seating/lockers/pigeon hole units /tables)	1	£8,000.00	£8,000.00
<u>PPA ROOM</u>			
Furniture	1	£2,000.00	£2,000.00
<u>GENERAL</u>			
Interactive Whiteboards for 8 Classes*	8	£3,500.00	£28,000.00
Internal & External Litter Bins*	1	£1,000.00	£1,000.00
External Play Equipment*	1	£50,000.00	£50,000.00
External Seating*	1	£4,000.00	£4,000.00
Fire Equipment*	1	£300.00	£300.00
Washroom Equipment*	1	£300.00	£300.00
Barrier Matting*	1	£1,000.00	£1,000.00
Miscellaneous items*	1	£2,000.00	£2,000.00
Contingency / Inflation.	1	£5,000.00	£5,000.00
		TOTAL	<u>£203,600.00</u>

NOTES

Items marked * may be included in the Building Contract.

Assumptions

That the following are all included in the Building Contract

(i) Intruder Alarm System/CCTV (ii) Fixed, Stock Cupboard and Classroom Storage Area Shelving (iii) Cloakroom Fittings (iv) Pinboarding (v) All floor finishes (vi) Data-cabling (vii) Door Entry Systems (viii) Signage (ix) Blinds

No allowance has been made for:

Computers for Administration and Pupils and all peripherals

APPENDIX D - Expansion Potential of Existing Primary/Infant Schools

Hitchin

School Name	Current Capacity (FE) at Reception	Expansion Potential (FE)
Samuel Lucas JMI	2	None
Highbury Infant School & Nursery	2	None
Highover JMI	2	None
St Andrew's CE VA Primary	1	None
Purwell Primary	1	None
Whitehill Junior	n/a	None
William Ransom Primary (The)	1.3	0.7*
Mary Exton JMI	1	1*
Wilshere-Dacre Junior	n/a	1
Strathmore Infant and Nursery	2	1
Oughton Primary and Nursery School	1	1
Our Lady's RC Primary	1	None
Ickleford Primary	1	None

*Requires detached playing field or MUGA

Letchworth

School Name	Current Capacity (FE)	Expansion Potential (FE)
Stonehill	1	1
Northfields Infant & Nursery	2	1
Hillshott Infant School & Nursery	2	None
Icknield Infant and Nursery	3	None
Norton St Nicholas C of E (VA) Primary	1	1*
Lordship Farm Primary	2	None
Garden City Academy	1	1
Wilbury Junior	3	None
Grange Junior	2	1
Pixmore Junior	2	None
St Thomas More RC Primary	1	1*

*Requires detached playing field or MUGA

Baldock Town

School Name	Current Capacity (FE)	Expansion Potential (FE)
St Mary's Infant and St Mary's Junior	2	1
St John's RC Primary	1	None
Hartsfield JMI	2	0.5

Royston Town

School Name	Current Capacity (FE)	Expansion Potential (FE)
Icknield Walk First School	2	1
Tannery Drift	1.5	1
St Mary's RC Primary	1	0.5
Studlands Rise First	1	None
Roman Way First	1.5	None

Knebworth

School Name	Current Capacity (FE)	Expansion Potential (FE)
Knebworth Primary	2	None

Stevenage Town North (Stevenage North West & Stevenage North East A)

Expansion Potential of Existing Primary/Infant Schools

School Name	Current Capacity (FE) at Reception	Expansion Potential (FE)
St Nicholas C of E Primary (Stevenage)	1	None
Almond Hill Junior	n/a	1
Letchmore Infants' and Nursery School	2	1
Fairlands JMI	3	None
Broom Barns Community Primary School	1	1
Bedwell Primary	1.5	0.5
St Vincent de Paul RC Primary	2	None
Woolenwick JM	n/a	None
Woolenwick Infant	2	None
Graveley Primary	0.5	0.5
Trotts Hill Primary and Nursery	1	1*
Martins Wood Primary	3	None
Round Diamond Primary	2	0.5*
Giles Junior and Giles Infant's School	2	1*
Leys Primary & Nursery School (The)	2.5	0.5 to 1*

* Requires detached playing field or MUGA or relocation of another HCC service

Expansion Potential of Existing Secondary Schools

Letchworth

School Name	Current Capacity (FE)	Expansion Potential (FE)
Fearnhill	6	Not known
Highfield (The)	6	Not known

Baldock

School Name	Current Capacity (FE)	Expansion Potential (FE)
Knights Templar	7	3

Royston

School Name	Current Capacity (FE)	Expansion Potential (FE)
Meridian (The)	7.1	Not known
Roysia Middle	3	Not known
Greneway (The)	4	Not known

Hitchin

School Name	Current Capacity (FE)	Expansion Potential (FE)
Hitchin Boys	5.3	1
Hitchin Girls	5.3	1
Priory (The)	6	3

Stevenage

School Name	Current Capacity (FE)	Expansion Potential (FE)
Thomas Alleyne (The)	6	*
Nobel (The)	8	*
John Henry Newman RC	7	*
Barclay (The)	6.5	*
Heathcote (The)*	n/a – school closed on 31 August 2012	*
Barnwell	10	*
Marriotts	8	*

* Any expansion potential in the existing schools in Stevenage is required to meet the immediate demand from the existing community.

8. SCHOOLS

Introduction

- 8.1 School provision is planned and monitored by Hertfordshire County Council's Childrens Services (CS) department. It has a duty to secure sufficient school places to meet demand and to promote diversity and choice. This provision includes primary, secondary, sixth-form education and special needs. Nursery places are managed and planned by Hertfordshire County Council's Early Years team.
- 8.2 The County Council also sees schools as playing a wider role in serving the needs of the community, through co-location of facilities and for other community uses. This is drawn from the wider national approach to children's services through the 'Every Child Matters' agenda and the Children's Act 2004. Agencies have a duty to work together to deliver integrated children's services with Children's centres and extended schools having a key role in delivering this requirement.
- 8.3 The County Council has a legal duty to secure sufficient school and early years places, to ensure qualitative education standards are met, to co-ordinate admissions and to provide Special Education Needs and Youth Services. However their role as the direct provider of education facilities is changing with an increase in Academy and Free School provision.
- 8.4 The Academies Act 2010 sought to greatly expand the number of Academy schools nationwide and introduced the Free Schools programme with the objective of providing a greater choice and better quality of education provision. There continues to be a rapid growth in the number of Academy and Free schools with significant implications for the planning of education provision
- 8.5 HCC has the responsibility for commissioning the provision of school places from a wide range of providers, but is the admitting authority in only one case (community schools). All other schools, including faith schools (which are either Voluntary Aided or Voluntary Controlled), federated schools (two+ schools under a single governing body), trust schools (those supported by charitable trusts), academies and free schools and independent schools, are not managed by them.
- 8.6 Where the need for a new school is identified, HCC must undertake a competitive process with the opportunity for the school to be a free school or academy first before they can provide a community school. Free schools, however do not have to be promoted on the basis of the need for school places and therefore have potential to distort basic needs planning.
- 8.7 Funding for schools has also significantly changed with the abolition of the Building Schools for the Future (BSF) programme and the implementation of the Priority Schools Rebuilding Programme. In addition, capital funding for schools will also be different. This is discussed in more detail in in the funding section below.

Existing Provision

- 8.8 Following a period of falling rolls, Hertfordshire is now experiencing an increase in demand for school places, particularly in the primary sector across the County. The County Council produces an annual report 'Meeting the Rising Demand for School Places' which sets out forecast demand and how this will be addressed. The report originally published in 2010 is currently updated on an annual basis.
- 8.9 To help inform and manage school planning activity, the County Council produces pupil forecasts twice per annum. The latest forecasts are set out in the Pupil Forecast (primary) and Pupil Forecast (secondary) produced in Summer 2013.
- 8.10 The forecasts are based on Education Planning Areas (EPA) and take account of actual numbers of 0 to 5 year olds sourced from GP registration data, known new housing developments and historic migration patterns. The forecasts set out the total Planned Admission Number (PAN) for each school and the actual number of pupils at 2012/2013 for direct comparison.
- 8.11 Planning for schools is volatile as there are many factors that can influence pupil numbers. In order to ensure an appropriate match between supply and demand for places taking into account both parental preference and fluctuations in demand, it is prudent to plan for a 5-10% surplus in an area.
- 8.12 The current forecasts are available at the website below. They have not been included in this IDP as they change frequently.
- <http://www.hertsdirect.org/scholearn/aboutstatesch/planning/>
- 8.13 Tables 6 and 7 below provide a summary of existing school provision and their ability to cope with current circumstances over the next 5 years. These have been derived from the most recent forecasts, as outlined above. The last column provides an indication as to whether additional school places would be required should there be further housing development.
- 8.14 The County Council has undertaken a study to look at the existing capacity of schools and their capacity for expansion if required. Appendix D contains the details of each school.¹ Current capacity and expansion potential is identified in this appendix in terms of it's FE (Forms of Entry; 1FE = 30 pupils). Expansion potential is defined as the number of additional FE that potentially could be accommodated on the existing school site. It must be stressed that this potential is a best estimate having regard to site size and relevant planning policies - in most cases no detailed feasibility work (e.g. on highways capacity) has been carried out to confirm the deliverability of any school expansion. It should also be stressed that the theoretical town planning capacity of a school to expand does not take into account the suitability of that location to meet need from an education perspective i.e. it would not be helpful to have primary or secondary capacity in a location that is poorly related to where new development is proposed. Unfortunately for some of the secondary schools the County Council has not yet been able to carry out the exercise necessary to consider their expansion potential.

¹ Information provided by Hertfordshire Property and Hertfordshire Childrens' Services, October 2013

Primary

8.15 North Herts has a total of 48 primary schools (including infant, junior and first schools). Most of the district operates a two-tier education system, with the exception of Royston which currently has a three-tier system of first, middle and upper schools. The first schools within Royston are included within this primary section.

Table 6: Summary of Existing Provision - Primary

Education Planning Area	Provision for the next 5 years to cope with current circumstances	Ability to cope with additional development
Letchworth	Limited capacity	None. Additional school places required
Baldock Town	Limited capacity	None. Additional school places required
Baldock Villages	Sufficient capacity	A local assessment would be required to consider the impact of any development in this rural area.
Royston Town	Surplus capacity	Two existing schools would have the capacity to take more children.
Royston Villages	Sufficient capacity	A local assessment would be required to consider the impact of any development in this rural area.
Hitchin West	Sufficient capacity	Limited development growth potential without having an impact
Hitchin South & North	Sufficient capacity Hitchin South Deficiency Hitchin North	None. Additional school places will be required
Hitchin Villages South	Deficiency	None. Additional school places will be required
Knebworth	Deficiency	None. Additional school places required
The Waldens, Kimpton Breachwood Green	Surplus capacity, except Breachwood Green	Yield from some further development could be accommodated. However, this would be limited
Codicote	Deficiency	None. Additional school places will be required.
Stevenage North West	Deficiency	None. Additional school places will be required
Stevenage North East A	Deficiency	None. Additional school places will be required

Secondary

- 8.12 North Herts has a total of 6 secondary schools within Letchworth, Baldock and Hitchin. Royston currently operates on a three-tier system with one upper school and two middle schools. The upper and middle schools within Royston are included within this secondary section.

Table 7: Summary of Existing Provision - Secondary

Education Planning Area	Provision for the next 5 years to cope with current circumstances	Ability to cope with additional growth
Letchworth	Sufficient capacity	Can accommodate
Baldock	Deficiency	None. Additional school places will be required
Royston	Surplus at the upper and middle at capacity from 2021/2022.	Can accommodate
Hitchin	Deficiency	None. Additional school places will be required
Stevenage	Deficiency from 2018/19	None. Additional school places will be required

Planned/Committed Provision

- 8.12 To deal with the deficiency of primary school places in Hitchin in 2013/14, the County Council has been granted planning permission to enlarge Samuel Lucas JMI by 1FE.
- 8.13 A previous reorganisation of primary school provision in Letchworth reduced the number of surplus primary school places in the town through the closure of Westbury and Lannock Primary Schools. Pupil numbers are now starting to rise and the County Council continually monitors demand to ensure there are sufficient places available to meet the need arising from the existing community. Icknield Infants and Wilbury Junior were expanded, along with Lordship Farm Primary to address a small increase in demand for places within the town for September 2013.
- 8.14 In Royston the published admissions numbers at Roman Way and Tannery Drift was reduced to 45 places in September 2011 reducing the number of surplus places in the town.
- 8.15 Hertfordshire's strategy for meeting the challenge of planning for rising rolls is summarised in the Meeting the Rising Demand for School Places document. This document identifies both the areas across the County where further capacity is required and the Local Authority's planned approach to addressing the deficit.
- 8.16 For further information:

<http://www.hertsdirect.org/services/edlearn/aboutstatesch/planning/>

- 8.17 In its role as commissioner for school places, the Local Authority will continue to work to ensure an appropriate level of school places across the County and will need to do so within the context of the current Government's agenda around diversity and choice through the promotion of Free Schools and Academies.

Infrastructure Requirements

- 8.18 The requirements for additional school places are set out in tables 8 and 9 below. These provide an estimate of the number of pupils that could be expected from the additional residential development in FE (i.e. a pupil yield of 30 children per 1 FE²). When undertaking high level school place planning related to new residential development (e.g. at Local Planning stage), a ratio of 1FE (210 pupils) per 500 dwellings is applied based on a study of 49 Hertfordshire developments undertaken by Hertfordshire County Council's (HCC) demographer (c 2008). This work produced a yield range of 1FE per 500 dwellings (42 children per 100 dwellings/97.5% confidence of not underestimating child yield) to 1FE per 850 dwellings (24.7 children per 100 dwellings/50% confidence of not underestimating child yield). The County Council applies the upper end of the range, 1FE/500 dwellings, in the first instance, for reasons of prudence.
- 8.18 The difference within the range is substantial and has significant implications for the cost of providing and funding school places. A range of 500 to 850 dwellings per FE has been given in this IDP to illustrate this difference. In reality the actual figure is expected to be somewhere between the two. The Council will need to work with the County Council to determine an appropriate balance between the range. Particularly in view of the educational requirements being a sizeable amount of the total infrastructure provision and the substantial range in costs. Equally it is also important not to under provide for education to ensure all future pupils have a school to go to. In any case, child yield calculations will need to be refined in the future when more detail is known regarding developments. This is because it is highly dependent on factors such as specific location of development, housing type and tenure, the amount of affordable housing and the amount of family housing proposed in a scheme. This flexible approach will be recognised in any systems set up for allocating funding through CIL, s106 or by other means.
- 8.19 Reference to primary pupil forecasts in the tables means a forecast of demand to 2016. Beyond this, growth of 10% in the existing population is assumed to the end of the Core Strategy plan period (2031). Primary pupil forecasts to 2016 include an assumed pupil yield from known new housing developments. For the purposes of infrastructure planning, the likely impact of housing option figures on school provision has been considered in addition to the pupil forecasts.

² (30 pupils in each of the seven years, gives a total of 210 pupils).

Table 8: Primary Schools

Area	Requirements		Costs
	Estimated Pupil Yield (Reception) based upon 1FE per 850 to 500 dwellings	Accommodating Additional Provision	
TOWNS			
Hitchin (including Ickleford)	1033 dwellings would generate 1.2 to 2 FE.	Additional school places will be required via expansion of existing schools	£4.81 to £8.02 million
Letchworth	897 dwellings would generate 1.1 to 1.8FE.	Additional school places will be required via expansion of existing schools	£4.41 to £7.22 million
Baldock	1328 dwellings would generate 1.6 to 2.7 FE.	Two new schools would be required.	£6.42 to £10.83 million
Royston	961 dwellings would generate 1.1 to 1.9 FE.	There is currently sufficient capacity and expansion potential in the first and primary schools to allow for forecast demand and estimated pupil yield from the proposed housing.	Costs will be covered by the existing capacity.
North Stevenage	2,300 dwellings would generate 2.7 to 4.6 FE.	There has been an increase in primary aged children living in North and North West Stevenage. The County Council is adding additional places into existing schools to cater for existing demand. One to two schools would be required as there is limited/uncertain capacity within the existing school estate to meet the demands from new housing.	£10.83 to £18.45 million
Great Ashby (NES3)	357 dwellings would generate 0.4 to 0.7 FE.	The additional dwellings would result in nearby schools being taken over their acceptable capacity thresholds. Further school expansion in the vicinity would be required to deal with this.	£1.60 to £2.81 million
RURAL			
Most schools within the rural areas can accommodate additional pupils without the need to expand. With the exception of the following:			
Codicote	125 dwellings would generate 0.15 to 0.25 FE	Current capacity tight. Additional school places will be required.	£0.60 to £1 million
Offley	68 dwellings would	Based on pupil forecasts, there is likely	£0.32 to

	generate 0.08 to 0.14 FE	to be a tight match between the level of demand and the current primary capacity in the one primary school in Offley. Additional school places will be required.	£0.56 million
--	--------------------------	--	---------------

Table 9: Secondary Schools (including Middle & Upper)

Area	Requirements		Cost
	Estimated Pupil Yield (Reception) based upon 1FE per 800 to 500 dwellings	Accommodating Additional Provision	
Hitchin (includes Hexton, Holwell, Ickleford, Langley, Lilley, Offley, St Ippolyts, Wymondley).	1254 dwellings would generate 1.5 to 2.5FE.	Additional school places will be required via expansion of existing schools	£4.76 to £7.93 million
Letchworth	897 dwellings would generate 1.1 to 1.8 FE	Additional school places will be required. There is currently sufficient capacity in the schools to allow for forecast demand and estimated pupil yield from the proposed housing.	£1.56 million for the 0.5 FE deficit by 2020/21.
Baldock(includes Ashwell, Bygrave, Caldecote, Clothall, Hinxworth, Newnham, Radwell, Rushden, Sandon, Wallington & Weston).	1,378 dwellings would generate 1.6 to 2.8 FE	Additional school places will be required via expansion of existing school	£5.07 to £8.88 million
Royston (includes Barkway, Barley, Kelshall, Nuthampstead, Reed, Therfield),	1,159 dwellings would generate 1.4 to 2.3 FE	Forecasts for the upper and middle schools suggest there is sufficient capacity across the town to meet forecast demand and estimated pupil yield from proposed housing.	Existing capacity.
North Stevenage	2,300 dwellings would generate 2.7 to 4.6 FE	New secondary school at Great Ashby – site of secondary school granted planning permission April 2010 should be designated as an education zone/allocation within the Local Plan to provide flexibility and ensure sufficient land is available to meet educational need	£8.56 to £14.58 million
Great Ashby NES3	357 dwellings would generate 0.4 to 0.7 FE	Secondary school pupils living in NES3 will most likely attend Stevenage secondary schools.	£1.27 to £2.22 million

		Additional school places will be required via expansion of existing Stevenage secondary schools or new school at Great Ashby.	
--	--	---	--

8.20 It should be noted that, at the primary school level, 2FE schools are CS's preferred model for new schools as they provide the opportunity to sustain educational improvement, enable the delivery of a broad curriculum, and have the critical mass of pupils to manage fluctuations in numbers. Hence, even if a development gives rise a need for only 1FE of additional capacity, the County Council's preferred option would be to identify a 2FE site. This will also ensure that the site is future proofed and is capable of expanding in the event that there is additional development proposed later in this plan period or a later plan period. It will therefore help to build in some inherent contingent education land supply. However, it is recognised that it will not always be possible to achieve this aim because it depends upon the availability of a suitably sized site in the right location.

8.21 CS's preferred model of secondary schools is 6-8FE (although it is acknowledged that smaller models of 4-6FE should not be discounted).

8.22 Further detailed discussions will need to take place in relation the provision of new and expanded schools. This will be an iterative process as more details are known. However, the information above provides a good basis for looking at strategic requirements.

Costs

8.23 The costs outlined in tables 8 and 9 above are based on child yield from proposed growth and a simple formula of £4.01 million per FE for primary and £3.17 million per FE for secondary schools³. However, in reality the provision of part of an FE is not practical and would not allow for flexibility in planning for schools. Therefore, in some cases the costs are likely to be significantly higher than identified to make up the shortfall in FE provision. In addition, costs will vary depending on whether a school is being extended or built from scratch, whether any land needs to be purchased (the cost of acquiring land has not been included), the specification/design and location. Extending existing schools may also impose a requirement to secure additional playing fields.

Comment [AD1]: See email of 30/10/13 re: updated costs

8.24 In view of the many variables for education, the costs given in this IDP cannot be set in stone and should just be viewed as a starting point. In summary, the range of costs for education are as follows:

School Type	Total Costs (million)	Total Costs (millions) Excluding 2011 planning permissions
Primary	£28.99 to £48.89	£25.71 to £43.56
Secondary	£21.22 to £35.17	£19.63 to £32.62
Total	£50.21 to £84.06	£45.34 to £76.18

³ Costs provided by Hertfordshire Property Secondary index base date Q1 2012 based on a new 6FE school. Primary index base date January 2011 based on a new 2 FE school.

Funding

- 8.29 The central government funding stream for providing additional pupil places is referred to as Basic Need. This is otherwise known as capital funding. The DfE calculate this based on an assessment of demand for additional places, and this varies from year to year. In the current year (2011?), basic need funding will meet about a third of the costs of the current primary school expansion programme. There is no funding settlement post 2012/13 and thus the level of any future Basic Need funding is unknown. However, an additional sum of £500m (nationally) will be made available in the financial year (2011/12) to help local authorities provide extra school places. Bids will not be required. Funding will be allocated on the basis of information already held by the department. It is hoped that some may flow to Hertfordshire and help support the current primary expansions programme.
- 8.30 The Building Schools for the Future (BSF) programme was one of the main sources of funding for improving existing secondary schools nationally and investing in new buildings in priority areas, such as Stevenage. However, in July 2010 the new government announced that this programme would cease and a major review of the schools capital investment programme would take place. This is known as the James' Review.
- 8.31 Following wide consultation, the group presented its final report and recommendations to the Secretary of State in April 2011. On 19 July 2011 Michael Gove published the government's response, saying that the recommendations of the review would be broadly accepted subject to a consultation process on details and implementation.
- 8.32 There were some important caveats within the Government's response when accepting the James Review recommendations. Most significantly there were reservations about the development of a single funding stream directed through the local authority. The Secretary of State is keen to ensure that such a scheme would not disadvantage any particular responsible body (e.g. individual academies) or become too bureaucratic. The move toward centralisation of procurement is likely to be implemented more slowly than first envisaged. This takes account of the many potential drawbacks of national centralisation when there are many existing good value for money procurement frameworks at local and regional level.
- 8.33 A new "Priority school rebuilding programme" will be launched instead of BSF, targeted at those schools in the worst condition. £2bn will be provided over 4 years to cover primary, secondary and special schools. It is expected that the funding will cover 100-300 schools in the poorest condition. Local authorities will be required to bid for funding for community, foundation and voluntary aided schools. Academies are able to bid either through a local authority or directly to the Department for Education. Hertfordshire officers have reviewed which schools might be put forward under this process and bids have been submitted.
- 8.34 The financial implications of the proposed changes are complex. In part they will depend on the relative condition of Hertfordshire properties to those nationally and the overall quantum of resource to be made available. But there is also a fundamental shift proposed away from allocation of substantial capital grant to the local authority to use at its own discretion. The

consultation proposes that 2012-2015 period would be used as a transitional period for the new arrangements. These changes add to the uncertain nature of planning for schools and how they will be funded.

Karen – to make things simpler you could remove paras 8.30 - 8.34 if you wish and just say something like:

8.35 The financial implications of the Government's proposed changes for Education are complex and at present not wholly clear yet . There is proposed, a fundamental shift away from allocation of substantial capital grant to the local authority to use at its own discretion, to free schools and academies. The consultation proposes that 2012-2015 period would be used as a transitional period for the new arrangements. These changes add to the uncertain nature of planning for schools and how they will be funded. In part they will depend on the relative condition of Hertfordshire properties to those nationally and the overall quantum of resource to be made available. The Government may make provision for other funding regimes, such as BSF and PSBP, which the County Council will seek to access as and when they become available.,

From: Ailsa Davis [mailto:Ailsa.Davis@hertfordshire.gov.uk]
Sent: 21 November 2013 10:42
To: Richard Kelly
Cc: Karen Allen
Subject: FW: Knebworth & NHDC long term housing

A similar position could be adopted with Codicote if land adjoining the school site came forward for housing.

Ailsa

From: Ailsa Davis
Sent: 21 November 2013 10:38
To: 'Richard Kelly'
Cc: 'Karen Allen'
Subject: Knebworth & NHDC long term housing

Hi Richard

This is the email I sent to Cllr Richard Thake when he was making enquiries last month about the expansion of Knebworth primary. This was sent following discussion with colleagues in Childrens' Services. The last para hopefully answers your question, but if you need further clarification do not hesitate to come back to me.

Thanks

Ailsa

From: Ailsa Davis
Sent: 08 October 2013 16:03
To: Richard Thake
Cc: Bethan Clemence; Kate Ma; Karen Crowhurst
Subject: Knebworth & NHDC long term housing

Richard,

I understand you spoke to my colleague Bethan Clemence yesterday in Childrens' Services regarding land to the south east of Knebworth, adjoining the primary school playing field in terms of whether it could assist in the expansion of the existing school as well as provide land for housing.

North Herts consulted last year on approx 1000 potential dwellings around Knebworth (see attached map from NHDC consultation). This includes the site you are referring to (site 57). Our reps advised that this level of housing would generate the need for a new 2FE primary school. Officers at North Herts have informally advised they would like any new school site to be located to the west of the railway.

I understand that the existing primary school is full and would be difficult to expand from a town planning perspective. However, if less housing were to come forward, say 500 units or less across the plan period to 2031 which included site 57, then this could assist in the expansion of the existing primary school if part of site 57 was given over to education use. There are no other reserve school sites in the village.

I hope this is useful, however if you require any additional information do not hesitate to contact me.

Regards

Ailsa Davis

Senior Planner, Development Services

Estate and Asset Management

Postal Point CHO315

Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DE

t: 01992 588275 Comnet / Internal: 28275

From: Ailsa Davis [<mailto:Ailsa.Davis@hertfordshire.gov.uk>]
Sent: 22 January 2014 10:43
To: Chris Carter
Subject: Site area for new schools

Hi Chris

The attached includes the range of school sizes (FE) for primary and secondary and gives ideal site area and team game space. For all through schools we are simply adding the two areas together as nothing from the Government has told us otherwise.

In summary:

2FE primary = 2.5h
3FE primary = 3h
6FE secondary = 9.7h
3FE primary and 6FE secondary all through school = 12.7h

Thanks

Ailsa Davis
Senior Planner, Development Services
Estate and Asset Management
Postal Point CHO315
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DE
t: 01992 588275 Comnet / Internal: 28275

From: Chris Carter [<mailto:Chris.Carter@north-herts.gov.uk>]
Sent: 21 January 2014 12:25
To: Ailsa Davis
Subject: Site area for new schools

Hi Ailsa,

Further to our meeting yesterday regarding the East of Luton sites, could you give me an indication of the amount of land that would be required for different size schools?

I know it is 2HA for 2FE and 3HA for 3FE at primary, what about a 6FE secondary or an all through school for 6FE secondary and 6FE primary?

Many thanks

Chris

Chris Carter
Senior Planning Officer

Direct Dial 01462 474477

North Hertfordshire District Council
Council Offices
Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF
chris.carter@north-herts.gov.uk
www.north-herts.gov.uk

Appendix A
HCC School Premises Space Standards

School Type	Size (fe)	Number of pupils	TOTAL CURRENT SITE practical site sizes m² (following BB99)	TOTAL CURRENT EXTERNAL TEAM GAME AREA Included as part of total site area. (following SPRs 1999) (m²)
PRIMARY	1fe	210	15,000	2,500
	2fe	420	25,000	5,000
	3fe	630	30,000	10,000
INFANT	1fe	180	7,000	None
	2fe	270	10,000	None
	3fe	360	13,000	None
JUNIOR	1fe	120	11,000	2,500
	2fe	240	16,000	5,000
	3fe	360	21,200	10,000

Note 10000 sqm = 1 hectare

School Type	Size (fe)	Number of Pupils (90% 6 th Form stay on rate)	TOTAL CURRENT SITE practical site sizes m ² (following BB99)	TOTAL CURRENT EXTERNAL TEAM GAME AREA Included as part of total site area. (following SPRs 1999) (m ²)
SECONDARY				
	4fe	816	71,000	40,000
	5fe	1020	84,000	45,000
	6fe	1224	97,000	55,000
	7fe	1428	110,000	60,000
	8fe	1632	123,000	65,000
	9fe	1836	136,000	75,000
	10fe	2040	150,000	75,000 +

Note 10000 sqm = 1 hectare

Appendix 3

HCC email to Stevenage Borough Council and others
with accompanying document setting out primary and
secondary education requirements

5 November 2014 August 2013 – January 2014

From: Bob Chapman [<mailto:Bob.Chapman@hertfordshire.gov.uk>]

Sent: 05 November 2014 14:47

To: Nigel Smith

Cc: David Hill; MartinPaine; Kate Ma; Alice Carrington; Sarah McLaughlin; Dick Bowler; Catherine Taylor; Peter Oddy

Subject: RE: School place forecasts for Stevenage Planning Area

Hi Nigel

I attach tables showing Primary and Secondary education requirements in SBC. I've included separate tables for the developments that directly adjoin the borough boundary, which are in NHDC and EHDC.

I've included some short explanatory notes at the end of the tables but thought it was worth expanding on the assumptions that are used for calculating how many fe (forms of entry) are required -

When undertaking high level school place planning related to new residential development, HCC determines child yield based on a ratio of 1f.e. per 500 dwellings to be 97.5% confident of not underestimating yield. This is based on a study of 49 Hertfordshire developments undertaken by HCC's demographer (c. 2008). This work produced a yield range of 1f.e. per 500 dwellings (42 children per 100 dwellings / 97.5% confidence) to 1f.e. per 850 dwellings (24.7 children per 100 dwellings/50% confidence). The County Council applies the upper end of the range, 1f.e.per 500 dwellings, in the first instance to ensure prudent planning (this is reflected in the tables , with the lower end fe requirement shown in brackets).

Therefore, for the purpose of responding to local plan consultations , HCC uses the above standard assumptions in calculating fe requirements (when considering actual proposals or planning applications, the County Council uses specific development forecasting models to ascertain more tailored demographic profiles, including pupil yields).

We're in the process of reviewing early years data but should be able to get something to you in the near future.

We would be happy to meet with you to discuss further.

Bob Chapman

Senior Planning Officer, Development Services Team

Property and Technology

Postal point CHO 313

Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN

Tel 01992 588116 **Comnet / Internal:**28116

Bob.chapman@hertfordshire.gov.uk

**SBC LOCAL PLAN HOUSING SITES
PRIMARY AND SECONDARY SCHOOL INFRASTRUCTURE REQUIREMENTS**

PRIMARY SCHOOLS

Ward Name and existing schools	Dwellings	Forms of Entry (fe) required	Infrastructure Required
Woodfield <ul style="list-style-type: none"> No schools 	1044	Greenfield development site of 800 dwellings (site ref. 610) generates 1.6 fe (1.2fe). Remaining 244 dwellings equates to 0.5fe (0.28fe) Therefore, the overall total requirement is 2.1 fe (1.48fe) NHDC propose 1000 dwellings on directly adjoining land (see In NHDC table below)	2fe school (site and building) as part of masterplan and required to be delivered 2017-2021. HCC would prefer the Greenfield development to come forward before development of other sites in the ward as the nearest existing schools are at or near to capacity
St Nicholas <ul style="list-style-type: none"> Leys Giles Inf. Giles Jnr. 	0	-	-
Martins Wood Old Town Pin Green (grouped together in light of location of existing schools) <ul style="list-style-type: none"> Trotts Hill Fairlands Letchmore Inf. Almond Hill Jnr 	357	0.7fe (0.42fe) requirement. Trotts Hill Primary may have potential to expand onto the adjoining Wisden Court EPH (HCC owned and which would need to be relocated). Other possibility is to convert Almond Hill Jnr to a Primary School - dependent upon results of feasibility work. Other schools at or near to capacity	1fe school expansion. Financial contributions required.
Chells <ul style="list-style-type: none"> Camps Hill 	17	0.03fe (0.02fe) required. Could be accommodated in existing school	Financial contributions required
Manor <ul style="list-style-type: none"> Lodge Farm 	52	0.1fe (0.06fe) required Could be accommodated in existing school	Financial contributions required

Ward Name and existing schools	Dwellings	Forms of Entry (fe) required	Infrastructure Required
Symonds Green <ul style="list-style-type: none"> • Woolenwick Inf. • Woolenwick Jnr. 	1411	Greenfield development site at west Stevenage - 1350 dwellings generates 2.7fe (1.58fe). Remaining other sites in the Ward generate 0.12fe (0.07fe) . No significant expansion capacity in existing schools	3fe primary school/s (sites and buildings) – could be either as one 1fe school and one 2fe school or a single 3fe school. Required to be delivered 2017 – 2021 as part of the masterplan for the development.
Bedwell <ul style="list-style-type: none"> • Bedwell • Broom Barns • St Nicholas (CoE) • St Vincent De Paul (RC) 	19	0.03fe (0.02fe). Could be accommodate in existing schools	Financial contribution
Town Centre (comprising parts of Bedwell, Roebuck and Old Town Wards) <ul style="list-style-type: none"> • No schools 	2700	5.4fe (3.2fe). High proportion of flatted development suggests lower child yield assumption is appropriate	3fe primary school/s (site and buildings) - could be either as one 1fe school and one 2fe school or a single 3fe school.
Bandley Hill <ul style="list-style-type: none"> • Ashtree • Featherstone Wood 	25	0.05 fe (0.03fe). Could be accommodated in existing schools	Financial contributions
Shephall <ul style="list-style-type: none"> • Peartree Spring 	50	0.1fe (0.06fe) required. No significant expansion potential in existing school but requirement is small so should be manageable	Financial contributions
Roebuck <ul style="list-style-type: none"> • Roebuck • St Margaret Clitheroe • Shephalbury Park 	87	0.17 fe (0.10fe)required. Roebuck due to be permanently expanded by 1fe from September 2015 subject to town planning permission. Additional fe requirement is small so should be manageable	Financial contributions
Longmeadow <ul style="list-style-type: none"> • Longmeadow (contiguous to Shephalbury Park) 	613	1.2fe (0.72fe) required. Could be accommodated either through expansion of existing school/s or new school on site refs. 604/609	1fe school (site and building) as part of master plan required to be delivered 2017-2021

IN NHDC	Dwellings	Forms of Entry (fe) required	Infrastructure Required
Land north of Stevenage (NS1)	1000	Directly adjoining SBC Greenfield site for 800 dwellings (site ref 610), NHDC propose 1000 new dwellings that equates to 2fe (1.12fe).	2fe school (site and building) as part of masterplan of the delivery of the development.
Land at NES 3 (GA1)	357	Current outline planning application. Possible need to expand The Leys by 0.5fe (being nearest school with expansion potential)	Financial contribution
Land north east of Great Ashby (GA2)	500	1fe (0.6fe) required. However, previous permission for secondary school on this land and there remains a need for this (in addition to 1fe primary school)	1fe school (site and building) as part of masterplan of development, with the capacity to expand to 2fe in light of demand from the existing new housing in this area.
Land west of Knebworth (KB1) <ul style="list-style-type: none"> • Knebworth 	227	Educational requirement should be considered in conjunction with directly adjoining site (KB2 below). Overall requirement is 0.82fe (0.26fe)	1fe school (site and building)
Land west of Knebworth (KB2) <ul style="list-style-type: none"> • Knebworth 	184	See Knebworth (KB1) above	See Knebworth (KB1) above
Land south of Cowards Lane, Codicote (CD1) <ul style="list-style-type: none"> • Codicote 	73	Educational requirement should be considered in conjunction with the two other Codicote sites. Overall requirement 0.36fe (0.08fe)	Financial contribution for school expansion. However, Codicote school is on a constrained site so new classrooms maybe difficult to accommodate. Also, a highways assessment indicates expansion would be difficult without significant highways mitigation measures.

IN NHDC	Dwellings	Forms of Entry (fe) required	Infrastructure Required
Garden Centre (CD2)	58	See south of Cowards Lane above	See south of Cowards Lane above
Land north-east of The Close, Codicote (CD3)	48	See south of Cowards Lane above	See south of Cowards Lane above
Land at Milksey Lane, Graveley (GR1) <ul style="list-style-type: none"> Graveley 	8	0.01fe (0.001fe). Could be accommodated in existing school	Financial contributions

IN EHDC	Dwellings	Forms of Entry (fe) required	Infrastructure Required
Land east of Stevenage	700	Self contained development on greenfield site - generates 1.4fe (0.82fe)	2fe school (site and buildings)
Villages within Stevenage school planning area (Windfalls)	100	0.2fe (0.1fe). Whether this can be accommodated in existing schools is difficult to assess without knowing the particular villages concerned and the amount of development proposed therein - more specific information on this would be helpful as there are constraints on school sites which would hinder expansion potential	Financial contributions.

NOTES

The tables do not take into account -

- the fe requirements from permission/completions to 31 March 2014 as these requirements are assumed to already be accounted for (by way of financial contributions in S106 planning obligations)
- the total Windfall allowance of 200 dwellings across the borough, which equates to a relatively small 0.4fe (0.6fe)

Primary school capacity

1 fe (form of entry) = 30 pupils. Therefore a 2fe primary school would have a capacity of 420 places (7 year groups x 30 places x 2fe). HCC's policy preference is for 2fe schools.

Feasibility studies are required to confirm the expansion potential of existing schools.

Calculation of fe requirement

The fe figures in the table are based upon a child yield assumption of 1fe per 500 dwellings, albeit the figure in brackets relates to a lower child yield assumption of 1fe per 850 dwellings. The two sets of figures therefore reflect a range of child yields.

SECONDARY SCHOOLS

STEVENAGE	Dwellings	Forms of Entry (fe) required	Infrastructure Required
<ul style="list-style-type: none"> • John Henry Newman RC • Collenswood (vacant) • Thomas Alleyne • Barclay • Nobel • Marriotts • Barnwell 	7593 (SBC)	15.1 fe (8.9fe) required across the town as a whole. Limited capacity in existing secondary schools except 5.3fe capacity at former Collenswood secondary school. Planned housing numbers on greenfield sites at north Stevenage by SBC (800) and NHDC (1857) indicate that land at Great Ashby should be reserved as an Education Zone in the Green Belt (for Secondary/all-through school).	Strategy for provision to be determined but may include school site at Great Ashby (sites and buildings) and/or expansion/reuse of existing school sites (contributions)

NOTES

The table does not take into account -

- the fe requirements from Permission/completions to 31 March 2014 as these requirements are assumed to already be accounted for (by way of financial contributions in S106 planning obligations)
- the total Windfall allowance of 200 dwellings across the borough, which equates to a relatively small 0.4fe (0.6fe)

Feasibility studies are required to confirm the expansion potential of existing schools.

Secondary school capacity

1fe (form of entry) = 30 places. Therefore a 6fe secondary school would have a capacity of 900 places (5 year groups x 30 places x 6fe), plus those students staying on into the sixth form (average staying on rate is 60% but is expected to rise). HCC's policy preference is for secondary schools of 6 to 10f.e.

Calculation of fe requirement

The fe figures in the table are based upon a child yield assumption of 1fe per 500 dwellings, albeit the figure in brackets relates to a lower child yield assumption of 1fe per 850 dwellings. The two sets of figures therefore reflect a range of child yields.

From: Chris Carter [<mailto:Chris.Carter@north-herts.gov.uk>]
Sent: 05 November 2014 15:55
To: Dick Bowler
Subject: North East Stevenage

Dick,

Further to our previous correspondence regarding the site at North East Stevenage, we have had a response from the promoter to the effect that his client does not control all of the required land for the access but that they are of the view that the other party involved (Weston settlement) would be prepared to come to a deal with them on their area of land.

At the moment we are seeking some comment on this from the trustees to the Weston Settlement but have not yet had a response.

Regards

Chris

Chris Carter
Senior Planning Officer

Direct Dial 01462 474477

North Hertfordshire District Council
Council Offices
Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF
chris.carter@north-herts.gov.uk
www.north-herts.gov.uk

Appendix 4

Email exchange between NHDC and HCC

8 December 2014 – 11 December 2014

From: Chris Carter [<mailto:Chris.Carter@north-herts.gov.uk>]
Sent: 08 December 2014 14:47
To: Dick Bowler
Subject: RE: North East Stevenage - land ownership

Dick,

Thanks for this. I will be happy to let you know what sort of response we receive once the consultation has taken place. I would just re-iterate that a comprehensive explanation of need and how the school would be delivered would be very useful to us. I appreciate that we have discussed these matters in person, but for completeness this would be useful for us in explaining any potential change in approach to the north east of Stevenage.

On a separate but related point, you may be interested to note that our proposals maps show an intention to remove the Priory School site from the Green Belt.

Best wishes,

Chris

Chris Carter
Senior Planning Officer

Direct Dial 01462 474477

North Hertfordshire District Council
Council Offices
Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

[Follow us on Twitter](#)
[Like us on Facebook](#)
www.north-herts.gov.uk

From: Bob Chapman [<mailto:Bob.Chapman@hertfordshire.gov.uk>]
Sent: 11 December 2014 15:38
To: Dick Bowler; Chris Carter
Cc: Nia Morgan
Subject: RE: North East Stevenage - land ownership

Hi Chris

I'll provide the explanation of need as part of our response to the imminent consultation on the Preferred Options draft Local Plan.

In terms of how new schools are delivered, Dick has advised me of the process set out below. An example of this in action is the Bishops Stortford North proposals at this link -

http://www.hertsdirect.org/your-council/civic_calendar/cabinet/18306278/ see Item 12

1. The volume of new housing development will have a child yield that needs a new school to be provided as the existing school infrastructure has/will have no capacity to absorb that yield and/or the location is unsuitable to meet the need.
2. The LPA should ensure that the planning permissions for those developments include planning obligations that, in combination, achieve a suitable site allocation for, land transfer for, and money contributions for, the development of the new school premises; or that the developers co-operate and provide a 'developer school' that is suitable and meets standards.
3. Separate the process of achievement of the new school premises from the process of how the organization that will operate the school will be brought into being.
4. Assume that the County Council can be the party that will receive the land transfer for, and the money contributions for, the new school premises; and that it will ensure that it is actually developed and ready for the operator.
5. And if 4 happens HCC would then lease the new premises to the new operator, under the standard DfE Academy lease - i.e. for 125 years at a peppercorn rent and use restricted to school purposes.
6. The summary taken from the new guidance (attached) on how 'new' schools are to come into existence is:

Key points

- The new "presumption" for an academy/Free School requires local authorities to seek proposals to establish an academy/Free School in the first instance where they identify a need for a new school.
- Local authorities must continue to plan for and secure sufficient schools for their area in line with their duties under section 14 of the Education Act 1996.
- Local authorities should assess the proposals they receive against the criteria in paragraph 12 below before forwarding all of the proposals to the Secretary of State. He will take into consideration any preference they indicate.
- Local authorities can no longer hold a school competition without the Secretary of State's consent, nor enter their own community or foundation school proposals into a competition.

- Despite the academy/Free School presumption, in certain exceptional circumstances it is still possible to publish proposals for a new maintained school outside of a competition, under sections 10 or 11 of the Education and Inspections Act 2006.
- The Secretary of State's consent is no longer required to publish certain proposals, including those for the establishment of new voluntary aided schools, primary schools resulting from infant/junior amalgamations, and new schools resulting from the reorganisation of existing faith provision.
- "Academy" is the legal term which also includes Free Schools of all types, University Technical Colleges (UTCs) and some Studio Schools, including 16-19 and alternative provision (PRU) establishments. This document uses "academy/Free School" as the collective term for these types of schools.
- "Proposer" in this document refers to the body or group that is proposing the new school.

7. And HCC is the 'promoter of last resort' of a new community school per bullet 5 above, should no satisfactory promotion of an academy/Free School occur.

8. So we are looking for the local planning authority at site allocations stage to ensure that the site needed is identified. And we would look to ensure that the local planning authority now and then uses its DC powers to ensure protection of and delivery of that site.

9. And in relation to the landowner[s] affected by the 'most suitable site', we would look for them to enter into a planning obligation to provide, free, such land and money contributions as their development child yield justifies, and beyond that we should ensure that in the s 106 agreement, or preferably a contemporaneous option to acquire - for legal and clarity reasons, there is provision for the balance of the site to 2FE capacity is purchased at fair value; and that balance is funded from other s106 contributions [or HCC cash flows in advance of receipt of those later].

10. Or the s106 for developer provided suitable school premises is transferred, lock stock and barrel [turn key solution] to a new education provider that that has been identified following the processes summarised at 6 above.

From this you will see that we view this matter as essentially a Planning Obligation lead process, for which we have much prior experience, and the part that differs is the process to identify the new school operator; and we can get on with the development processes making the assumption that Education processes will follow in due course.

I hope that this is helpful.

Regards

Bob Chapman

Senior Planning Officer, Development Services Team
 Property and Technology
 Postal point CHO 313
 Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN
 Tel 01992 588116 **Comnet / Internal:28116**
Bob.chapman@hertfordshire.gov.uk

Appendix 5

HCC letter to NHDC regarding all-through school provision with accompanying appendices.

10 July 2015

Deputy Chief Executive
Director of Performance and Resources



Mr S. Ellis
North Hertfordshire District Council
Council Offices
Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

Hertfordshire County Council
County Hall
Hertford
SG13 8DE

Telephone: 01992 588132
EMail Alexandra.stevens@hertfordshire.gov.uk
My ref: AM01/241
Your ref:
Date 10th July 2015

By Email

Location: Wandon Park, Luton (Also known as “Land East of Luton”)

Proposal: A mixed use development incorporating residential, retail, education and community facilities (A1-A5, C3, D1, D2) and associated development; associated roads; open space, green infrastructure and ancillary facilities – in outline.

Dear Mr Ellis

Further to our meeting on 8th June I have set out Hertfordshire County Council’s (HCC) response to the above proposal in respect of Education Services below. HCC also seeks provision towards its other services however these are the subject of separate correspondence.

As discussed, the most challenging aspect of this proposal being how to ensure the sustainability of a development of only approximately 1,050 dwellings in this location in the absence of a Master Plan for this potential housing area which could deliver 2,050 dwellings.

Background

HCC last formally responded to this application in June 2014 stating it needed to object to the proposal at that time due to the lack of a suitable means of effectively managing the secondary education need which would be generated by the development.

Discussions on this proposal continued and the applicant offered the possibility of a site for an all through school comprising 2 forms of entry (fe) at primary which could potentially address the anticipated primary need from the remainder of the proposed housing allocation and 4fe at secondary level, which could cover the anticipated secondary need from both the current application and potentially that of the remainder of the area should it come forward.

An illustrative plan of the standalone primary school was provided to HCC in February with additional plans showing the possible all through school provided at the end of February, in advance of a site visit in March. Initial comments were passed back to the applicant on 11th March. Internal discussions also continued with possible solutions being analysed. This culminated in a meeting with you on 8th June. (I have included the formal capacity review of the plans provided at Appendix 2)

Modelling the child yield from this proposal has also continued with reviews of the mix occurring in August 2014 and revisions made to the trajectory in February 2015. More recently, additional scenarios have been undertaken exploring the requirements in the event this site did not come forward in isolation but in combination with either or both of the other areas making up this potential housing allocation.

The current application for 1,050 dwellings based on an assumed mix and trajectory (50 dwellings in the first year followed by 100 for the next 10 years) results in the following anticipated need for school places:

Primary

Peak yield of 1.98fe

Long term average of 1.21fe.

Secondary

Peak yield of 1.89 fe

Long term average of 1.11 fe

Amending the original assumptions to take a revised trajectory into account only slightly changes the peak yield to 1.92fe at primary and 1.84fe at secondary.

Site Location

The location of the above proposed development must be considered, particularly in relation to what existing schools may serve this potential residential site and the ability of those schools to accommodate children from new housing.

As previously identified, at primary level current school forecasts indicate it would not be possible for children from this proposal to be accommodated within the nearest existing Hertfordshire schools, which are predominantly in rural locations serving small local communities. Based on discussions with Luton Borough Council (LBC) it is also

understood that children in this age group could not be accommodated within Luton primary schools.

The nearest Hertfordshire secondary schools are in Hitchin, approximately 6 miles from the site. This site falls mainly within the Hitchin priority area for admissions purposes. Secondary schools in Hitchin are all full at year of admission and current forecasts indicate a need for additional places to meet rising demand from the existing community. Although there is some potential to expand provision on existing sites, information to date indicates this latent capacity is needed to meet the needs of both the existing population and planned growth within Hitchin.

Alternatively, future residents of this proposal may look towards secondary schools in Harpenden however, these existing schools are full and oversubscribed with pupils living closer. Pupils arising as a result of this proposed development would not therefore gain a place in a Harpenden school, based on existing patterns of admissions and demand.

It is also understood from LBC that all Luton secondary schools are full or forecast to be full and any opportunities to the expand capacity of these schools will be required to accommodate existing need.

Proposed development and education requirements

The current proposal is for a development of up to 1,050 dwellings. However the potential housing allocation is for approximately 2,000 dwellings, being made up of a further two parcels, one of approximately 600 dwellings and the other 400.

In terms of the scale of the current application, modelling of the child yield to date indicates approximately 2fe of primary need would be generated. HCC's preferred size of primary school is also 2fe being considered sustainable in terms of numbers of children, economic efficiency and also curricula. Accordingly, this need can be addressed via an on-site solution where a suitable, appropriate site is provided along with the funds to develop the 2fe primary school. (A Land Specification for a primary school has been included below at Appendix 1)

The situation is not as straight forward at secondary level with the current application generating a need of approximately 2fe and HCC's preferred approach is for secondary schools of 6-10fe based on curricula offer and economic efficiencies. Where a secondary school of this size cannot be provided and existing schools cannot be expanded, secondary provision can be made via all through schools. HCC believes the minimum size of all through school consists of at least 2fe at the primary phase and 3-4fe at the secondary phase. Less than this would not be considered educationally viable to provide the breadth or depth of curriculum opportunities at KS4 and beyond, in addition small schools are at a greater risk of financial viability issues and the impact of fluctuations in demand, particularly in light of the rising budget pressures schools are experiencing.

Analysis of the existing population of primary age children living in neighbouring rural settlements who would live closer to a new secondary school within Wandon Park than to any other Hertfordshire school, is estimated to be approximately 1.5f.e. However, it is unlikely that this new school would draw significantly from the existing surrounding communities as patterns of parental preference for single sex provision and faith provision are likely to continue to be strong. There is a significant risk that an all-through school solution would not attract sufficient numbers of children required to make the school sustainable. It could be assumed approximately 1fe may be generated by the existing population, which could increase demand coupled with the yield from the Bloor Homes development to approximately 3f.e. but this would not provide sufficient demand to effectively support and sustain an all-through school solution. As a result, simply relying on sufficient numbers of children from the surrounding area to choose this school is not considered a viable option which could be supported with County Council capital investment.

Having considered this matter in detail and finding there are no suitable options to effectively manage secondary education provision from this standalone application, HCC can only suggest this matter is dealt with through long term spatial planning processes to ensure that any development taking place east of Luton is of sufficient scale to warrant provision of a new secondary school. Such a development would need to comprise at least 2,000 dwellings in order to support a new secondary school of an appropriate size to offer viable education provision for the new community it will serve.

Options to enable this development to be sustainable for secondary education

As identified above, 2 fe would be required at secondary level. The nearest Hertfordshire secondary schools are full at year of admission and current forecasts indicate a need for additional places to meet rising demand from the existing community. The closest secondary schools to the development are in Luton but any existing capacity within these schools is part of Luton's strategy to meet the pressure for secondary places in the south/centre of the Borough and it is therefore not possible to rely on capacity at these schools to meet the yield arising from this proposed development.

The applicants have offered an area of land for an all through school i.e. a school with 2fe at the primary phase and a 3 to 4fe secondary phase to address the secondary demand from the development and also from neighbouring settlements. However as explained above, this is not considered a viable option.

The draft Local Plan identifies this area for the development of approximately 2,050 residential dwellings comprising 1,050 dwellings within the current application, 400 dwellings on additional land under the control of the applicant and 600 dwellings on land owned by a third party. Extending the previous modelling to include either or both of these additional sites results in the following scenarios. (Details of the previous modelling work and the applied HCC child yield model in general is included within HCC's response dated 5th June 2014)

Scenario 1: Wandon Park & 400 dwellings

Extending the previous model to increase the total number to 1,450 dwellings (i.e. Wandon Park proposals plus 400 dwellings on land under the applicant's control) using the Wandon assumed mix as a base and with the 400 dwelling scheme commencing after the Wandon Park proposal, results in the following child yield:

Primary

Peak yield of 2.47fe

Long term average of 1.7fe.

Secondary

Peak yield of 2.39 fe

Long term average of 1.56 fe

Outcome: This scenario would result in the need for 3fe at primary and approximately 3.5fe at secondary if the secondary pupils from the surrounding villages are taken into consideration. A development of this size would call into question the financial and educational sustainability of the secondary element of an all-through provision, particularly if the long term average is ever reached. This scenario is not ideal given the reliance on secondary aged children choosing to attend from the surrounding villages.

Scenario 2: Wandon Park & 600 dwellings

Extending the previous modelling to increase the total number to 1,650 dwellings (i.e. the Wandon Park proposals and the 600 dwellings on third party land) using the Wandon Park assumed mix as a base with the 600 dwelling scheme commencing 2 years after commencement of the Wandon Park proposal (as there is currently no application in respect of this area of land) , results in the following child yield:

Primary

Peak yield of 3.19fe

Long term average of 1.94fe.

Secondary

Peak yield of 3.06 fe

Long term average of 1.79 fe

Outcome: This scenario would result in the need for just over 3fe at primary and approximately 4fe at secondary once the secondary pupils from the surrounding villages are taken into consideration. This scenario could potentially meet the minimum size for the secondary element of an all-through school although it is borderline and therefore

presents sustainability risks particularly if the long term average is ever reached. However, this scenario is not ideal given the reliance on secondary aged children choosing to attend from the surrounding villages.

Scenario 3: Wandon Park & 1,000 dwellings

Extending the previous modelling to increase the total number to 2,050 dwellings (i.e. the whole area is developed) using the Wandon Park assumed mix as a base with the 600 dwelling scheme commencing two years after the Wandon Park proposal and the remaining dwellings being built at the end of the Wandon Park development, results in the following child yield:

Primary

Peak yield of 3.49fe

Long term average of 2.43fe.

Secondary

Peak yield of 3.58 fe

Long term average of 2.23 fe

Outcome: A development of 2,050 dwellings in this area would create sufficient demand for school places to enable a secondary school to be viable in the long term. This scenario combined with approximately 1fe from the surrounding villages, would result in the need for 4.5 - 5fe at secondary and up to 4fe at primary.

Although it is possible to deliver primary provision in the form of a 2/3fe school or two 2fe schools depending on which combination of applications come forward, this is not the case for secondary provision.

In the event the Wandon Park proposal is built in isolation, there would not be sufficient numbers of children to maintain a sustainable secondary education school and there are no alternative existing secondary schools which could accommodate the yield from this proposed development. In addition, the possibility that 40 of the proposed houses will be retirement dwellings thereby reducing the above figures yet further, must also be taken into consideration.

Wandon Park needs to be developed through a Master Plan approach, in conjunction with the additional housing potentially being allocated for development within this area.

In order to be confident any secondary provision will be sustainable in the long term, all three development sites (2,050 dwellings) should be developed together and Master Planned to ensure the correct quantum and timing of the required infrastructure, in addition to its long term sustainability.

The need for a Master Plan approach

The above highlights the issues faced by HCC in respect of trying to ensure there are sufficient school places for a development of 1,050 dwellings in this location given the current situation regarding school capacity, particularly at secondary level.

Increasing the number of dwellings such that there would be a sufficient number of children to sustain a new secondary provision, either in the form of an all-through or a standalone school, is essential in order to secure the sustainability of development in this area in respect of education.

To be confident that this can be achieved, HCC recommends that development is only allowed to come forward as part of a Master Plan approach which would cover the scale and timing of the development as well as the infrastructure necessary to support it, including triggers for payment of contributions and transfer of land. Accordingly HCC would also like to stress the need for a single Section 106 deed to govern the development of this area.

HCC has previous experience of attempting to deal with large scale development where the area in question has been the subject of two separate applications and the respective applicants were not willing to work together to achieve a sustainable, coordinated approach to infrastructure provision across the site. This resulted in difficult drawn out discussions regarding education provision and ultimately a less than optimal configuration of onsite school provision included within the Section 106 completed in relation the first site. The second site being subsequently refused at Committee will now be the subject of an appeal at the same time as a second application on the site is submitted for approval. The arrangement of schools has implications for HCC in terms of efficiency and generates concerns regarding the long term sustainability of the 1fe primary schools. This issues also have implications for the future residents who may also ultimately have new schools with less curriculum opportunities. As a result HCC is still attempting to work with the developers of both sites to improve the situation by varying the existing Section 106 and including options regarding the education solution in respect of the second site.

Conclusion

HCC would like to reaffirm its previous comments that this area needs to be Master Planned as a whole to coordinate the provision of both the residential development and the infrastructure to support it.

The development of 1,050 in this location at this time should be avoided. If this area is to be developed for housing it should be of sufficient quantum to sustain a new secondary school provision.

HCC believes the best approach for delivering development at this location would be via a single Section 106.

I trust the above is of assistance however, please contact me if you require any further information.

Yours sincerely

Alexandra Stevens
Planning Obligations Officer
Development Services
Property Department

Potential all through school at Wandon Park

Capacity Review of indicative plans from Steve Clyne

Site Visit

A site visit has been undertaken by HCC Development Services and Strategic Asset Management Team and land parcels A, B and C were visited. It would appear that land parcel B is the most appropriate for a school site with regard topography and land levels, obviously further feasibility studies would need to be undertaken. The land does slope toward the woodland area on parcel B and some levelling may be required for playing field areas.

Parcel C is relatively flat and would appear to be appropriate for pitch layouts. The indicative site layout plans produced by the Developers show one pitch on parcel C, it is possible that more of that parcel will need to be given over to school playing fields following further feasibility studies. The plans show a new road cutting across parcel C and thus if further pitches were to be located on parcel C it would be a split site.

Site Capacity

The information from Steve Clyne presents a site area of 62,842 m² for the all through school on parcel B with one pitch on parcel C. I have calculated that following BB103 an area range of between 64,346 m² (6.4 ha) to 80,630 m² (80.6 ha) is required for an all through school providing for 4FE of Secondary education and 2FE of primary education. This calculation does not take into account any shared provision of building or external areas. If shared provision of areas is designed into a scheme then the total area could possibly be reduced. I arrived at these areas by calculating a 4FE Secondary (780 NOR including a 75% stay on rate) plus a 2FE Primary School site area (480 NOR including at 60 place nursery). All areas have been calculated using BB103 formulas which gives a range for site areas.

It would appear that the area of 6.3 ha is just short of the lower range for an all through school (2FE + 4FE) but the site size could be reduced if the school buildings are spread over several floors (more than two levels) and if MUGAs and/or all weather pitches were provided. The site area could also be reduced if the Secondary School and Primary School were to share some internal facilities and external playing field. A design scheme will need to

be worked up by the architects to see if all the facilities could fit within parcel B land with one pitch on parcel C and if the multi-storey building was acceptable in that location. .

5Fe and 6Fe expansion

If the school is to be future proof and accommodate 5fe or 6fe of pupils then the buildings and site areas will increase. The table below shows the variance in area showing a range from min to max as provided by BB103 guidelines.

BB103 Standard Areas

4FE Secondary 2FE primary all through school		
Combined site area	m ²	ha
min	64346	6.4 ha
max	80630	8.1 ha

5FE Secondary 2FE primary all through		
Combined site area	m ²	ha
min	74096	7.4 ha
max	92915	9.3 ha

6FE Secondary 2FE primary all through		
Combined site area	m ²	ha
min	83846	8.4 ha
max	105200	10.5 ha

Attached is a table that provides the various external areas required on the site but no indicative plans have been drawn up to illustrate these different schemes. It is possible that in order to increase the secondary level to 5fe or 6fe that all of parcel C will be required or possibly more. It could also be that a dpf will be required elsewhere if the remainder of parcel C is required for residential development.

Building Capacity

Using the EFA SoA to work out the total GIA of the school buildings the area required for a 4FE secondary schools is min GIA of 6,440 m² and a 2FE primary school will require a total

min GIA of 2,318 m². This would give a combined total area of 8,758 m². The developers calculation includes 4,234.8 m² for building footprint which is divided into 2,398 m² for a 2 storey secondary wing and 1,248 m² for a single storey primary school wing . These areas are smaller than the minimum recommended area given in the EFA's SoA toolkit. It would appear that the buildings will require more land take unless they are higher than two storey, if that is appropriate for this development and is agreeable with Children's Services.

End.

HCC Review of land areas for potential all through school

Wandon Park School Site Areas

Secondary Schools

BB 103 Guidelines	
	4FE (75% stay on rate)
	NOR
	780
Recommended min site areas for all schools	
soft outdoor PE	33300
hard outdoor PE (court)	1570
soft informal and social area (inf rec)	2160
hard informal and social area (playground)	980
habitat	390
float	4700
min net area	43100
non-net	7460
min total site area	48000
Maximum net site area	48000
Maximum total site area	60140

Building Size (BB103 SoA Formulas)	4FE (75% stay on rate)
Range Total Gross	
Min	6440
Max	7413

Primary Schools

BB 103 Guidelines	
	2FE (7 classes)
	NOR
	420
Recommended min site areas for all schools	
soft outdoor PE	8400
hard outdoor PE (court)	1030
soft informal and social area (inf rec)	1440
hard informal and social area (playground)	620
habitat	210
float	2700
min net area	14400
non-net	1736

min total site area	15986
Maximum net site area	15986
Maximum total site area	20040

Building Size (BB103 SoA Formulas)	2fe primary
Range Total Gross	
Min	2318
Max	2560

5FE (75% stay on rate)	6FE (75% stay on rate)
NOR	NOR
975	1170
40125	46950
1862.5	2155
2550	2940
1175	1370
487.5	585
5675	6650
51875	60650
8825	10190
57750	67500
57750	67500
72425	84710

5FE (75% stay on rate)	6FE (75% stay on rate)
7700	8960
8831	10250

2FE Nursery	Total Areas
NOR	NOR
60	480
0	8400
0	1030
120	1560
60	680
0	210
120	2820
300	14700
60	1796

All through school

4FE Secondary 2FE primary all through	
Combined site area	sqm
min	64346
max	80630

5FE Secondary 2FE primary all through	sqm
Combined site area	
min	74096
max	92915

6FE Secondary 2FE primary all through	sqm
Combined site area	
min	83846
max	105200

360	16346
360	16346
450	20490

ha
6.4 ha
8.1 ha

ha
7.4 ha
9.3 ha

ha
8.4 ha
10.5 ha

Appendix 6

HCC email to NHDC with Stevenage Secondary
Education Need Paper to NHDC

8 December 2014 – 11 December 2014

From: Alice Carrington [<mailto:Alice.Carrington@hertfordshire.gov.uk>]
Sent: 19 August 2015 12:37
To: Chris Carter
Cc: Kate Ma
Subject: Stevenage Secondary Education Need

Hi Chris

Apologies again for the delay sending this through to you, but finally attached is the Stevenage Secondary Education Need paper.

I will also send a copy to Nigel Smith and Caroline Danby at Stevenage Borough Council.

I hope you enjoy reading and any questions let me know!

Thanks

Alice

.....
Alice Carrington

Planning Officer, School Planning (East)

Children's Services

Postal Point CHO134

Hertfordshire County Council, Room 138, County Hall, Pegs Lane, Hertford, SG13 8DN

Telephone: 01992 555725 (Comnet/Internal: 25725)

Stevenage Secondary Education Need – August 2015

Stevenage Secondary Need

Background

The County Council's previous school planning strategy for Stevenage was formulated in the context of the previous Government's Building Schools for the Future programme which was to provide a significant capital investment into rebuilding or extensively remodelling the secondary schools in the town. The strategy involved rationalising and expanding provision to meet the future need for secondary places, including the relocation of one school to a new site to the north of the Great Ashby development. This would have provided a pattern of 8 Forms of Entry (FE) secondary schools, with the exception of John Henry Newman School whose Governing Body at that time took the decision not to take part in that strategy.

However, with the Government's abolition of this programme in 2010, this strategy became undeliverable financially. Funding for only the two sample schools survived. Building schemes at The Nobel School and Marriotts School (which included the co-location of Lonsdale Special School) have seen both schools rebuilt or significantly refurbished and expanded in capacity to 8FE.

Separately, Barnwell School, currently at 9FE, which serves the south of the town, has received capital investment from the County Council to expand its buildings to enable it to offer 10FE in the future. Its occupation of the Barnwell East site (formerly known as Collenswood School) ceased at the end of the 2013/14 academic year, and it now operates over its existing main site and its neighbouring site, formerly Heathcote School.

Current places available

Stevenage Education Planning Area (EPA) therefore is currently served by six secondary schools offering 1366 Year 7 places.

The current admission numbers for 2015 for the 6 secondary schools are as follows:

	Published Admission Numbers (PAN) 2015	Forms of Entry (FE)
The Barclay	196	6.5FE
Barnwell	270	9FE
John Henry Newman (JHN) (Catholic)	226* (240)	7.5FE* (8FE)
Nobel	240	8FE
Marriotts	240	8FE
Thomas Alleyne (TAS)	180	6FE
TOTAL	1352* (1366)	45FE* (45.5FE)

(*JHN offered 240 places by local agreement for September 2015, & plans to permanently offer 240 places from September 2016)

The area also has a Studio School offering 90 places from admissions at Year 10.

A map of the secondary and studio schools in the town is attached at Appendix A.

Pupil dynamics

Historically, there has been around a 6% net inflow into Stevenage at secondary transfer, mainly as a result of children from outside the area seeking faith provision and attending the John Henry Newman Catholic School (JHN).

A number of pupils do choose to travel outside of the town for their secondary education, attending single sex schools in Hitchin or Hertford & Ware or travelling into the three tier system in Buntingford. However, due to changes in admissions criteria and rising demand in outlying adjacent areas, this outflow is likely to reduce in the future.

Although no impact on Year 7 places, The Da Vinci Studio School, which opened in September 2012, offers education provision for 14 – 19 year olds and currently has 136 pupils on roll in Key Stage 4. 68% of these pupils live within the Stevenage secondary EPA. 30% of Year 10 students come from outside Stevenage.

Existing population

Stevenage has seen growth as a result of new housing, particularly to the north and west of the town.

Analysis of changes to the existing demographic suggests a very significant increase (60%) in the cohort size living closest to Thomas Alleyne (TAS) & Barclay Schools when current Year 7 pupils are compared with the pre-school aged population. The number of places offered at TAS & Barclay provides a good match to meet the future need from that area.

There are also currently around 15FE of pre-school aged children for whom Nobel is their closest school. This includes the new housing around Great Ashby where currently around 7FE of secondary aged and around 10fe of pre-school aged children live.

Further south in the town, Barnwell and Marriotts provide 18FE of Year 7 places with around 20FE of children for whom they are their nearest schools. Taking into account parental preference and the faith offer in the town (with Stevenage pupils attending JHN from across the town), this indicates an appropriate level of provision currently to serve the communities in the southern part of Stevenage.

Forecast demand

Primary

Additional primary provision has been provided to meet the recent significant increases in the primary population in Stevenage. 4FE (120 reception places) has been added in the north and west of the town since 2011, and a further 1FE (30 reception places) in the south east at Roebuck Primary School (from September 2015); a total of +5FE of additional permanent capacity to date. This will result in a total of 1400 reception places being available across the Stevenage area as a whole to meet increased need.

Current primary forecasts indicate this will provide sufficient capacity to meet forecast demand, although it is worth noting that these forecasts are based on actual pre-school aged children and therefore only extend four years into the future.

As these cohorts work their way through their primary school years, the increase will begin to impact on secondary demand.

Secondary

There is currently 6FE of spare Year 7 capacity (with Barnwell School at 9FE) which is mainly concentrated in Barnwell School in the south, with some capacity also in The Barclay School in the north west of the town.

However, the latest summer term forecast 2015/16 indicates the rise in population coupled with likely housing growth sees a deficit of Year 7 places from 2019. Should Barnwell offer an additional +1fe and expand to its full built capacity [10FE], the forecast indicates all Year 7 places will be full and demand will exceed the places available in 2021.

Based on current places available, latest forecasts indicate a need for an additional 3FE of Yr 7 capacity in 2021/22, rising to a peak demand of around 5FE across the town in 2023/24.

This forecast includes an assumed pupil yield from new housing growth that continues to remain uncertain pending Stevenage Borough Council's (SBC) progression of its Local Plan process. It should be noted that HCC's pupil forecasts only extend 10 years into the future, beyond which children requiring a secondary school place are not yet born. Housing growth beyond 2025/26 and the needs arising from this are not taken account of within these pupil forecasts.

As a sanity check, if no housing growth was included at all (which is unlikely), modelled forecasts suggest forecast demand peaks in 2022/23 with all schools full at Year 7 (assuming current admission numbers and Barnwell's capacity at its expanded 10FE) and longer term around 5% surplus capacity to manage fluctuations in demand.

With no new housing therefore, the current capacity along with the expansion capacity at Barnwell by 1FE, provides appropriately for the rising demand from the existing community.

Pupil yield from housing growth

SBC has recently advised that it is continuing to work towards a new local plan for Stevenage to cover the period to 2031. New population projections recently released by the Government point towards future housing numbers significantly higher than those proposed in its first consultation on its plan in 2013 and this is currently being considered by SBC.

The most recent indication from SBC is a significant housing growth target of potentially 7600 new homes between 2011 and 2031. If an even trajectory of house building was assumed, this would equate to 380 per annum. As this total figure includes dwellings already built, the remainder to be built would be 6073 (assuming 380 per annum between 2011 and 2031 2015). In addition, there is proposed growth to the north of Stevenage within the NHDC boundary (1857 dwellings). Together this indicates total new housing growth of 7930 to 2031.

Working on a range of 500 to 850 new homes equating to 1 form of entry (FE) of pupils, this suggests a pupil yield from new housing of between 9FE and 16FE.

Further work is required on timescales and phasing to determine peak yields.

Although the scale of further housing growth remains uncertain, there is a need, based on the advice provided to date, to identify up to 16FE of additional secondary education capacity to ensure future needs of the town can be met.

Potential capacity available across the town

Property feasibility work on existing school sites confirms around 3.5FE of potential additional capacity is possible within the current school sites. Further buildings would be required at both TAS & Barclay to enable the schools to take more pupils. Barnwell has a current PAN of 270 and has the building capacity to expand to 300.

School	Type	Current PAN	Expansion potential	Comments
Barclay	Community	6.5FE	0.5FE	Possible to expand to 7FE. However the school would be deficient under S77 regarding all playing fields but it would be compliant on the soft outdoor PE (BB103).

				To expand beyond 0.5FE it would require additional land.
Barnwell School (combined middle and upper)	Community	9FE	1FE	This site would not be compliant on soft outdoor PE (BB103) or following S77.
John Henry Newman	Academy	7FE	0FE	Reviewed at current capacity of 7FE this site is currently deficient on soft outdoor PE (BB103) and S77 standards. Any expansion would require additional land.
Marriotts (& Lonsdale)	Community	8FE	0FE	Current capacity at 8FE and would require additional land to expand and meet standards.
The Nobel	Community	8FE	0FE	Current capacity at 8FE and would require additional land to expand and meet standards.
Thomas Alleyne	Academy	6FE	2FE	The existing access into the school is quite restricted and there doesn't appear to be great scope to improve it, particularly at the junction with the High Street. Because of this limitation, it is likely the existing car park would need to be significantly enlarged/reconfigured to accommodate not only additional staff parking but also drop-off/pick-up facilities. Some the school playing fields would be required to enable this. Further feasibility work required to confirm expansion potential.
POTENTIAL TOTAL			3.5FE	Further feasibility required to confirm

CAPACITY (existing school sites)				expansion potential at existing sites
Former Barnwell East (previously Collenswood)	n/a	0FE	5FE	This site is slightly deficient at 5FE following BB103 areas and S77. It could become compliant with some all - weather surface areas.


Potentially, up to 3.5FE of possible capacity may be available at existing school sites across the town (although the +1FE at Barnwell may be required to meet the needs of the existing community).

If this can be achieved, this leaves a further requirement for 5.5 FE – 12.5FE of additional secondary capacity to meet long term need arising from new housing growth. The former Barnwell East site could assist in meeting some of this need but, even with the 5FE it offers, additional capacity is still required to ensure sufficient secondary places for the long term.

Conclusions

- Need to secure the former Barnwell East site for future secondary provision. This would offer 5FE of secondary capacity.
- Need to identify a further new 8FE secondary site to ensure sufficient potential for the remaining additional demand that may arise.
- Based on existing demographic, a new 8FE school site to the north of the town, on the previously identified site north of Great Ashby, would provide for an appropriate pattern of secondary provision to meet the local demand.

Stevenage secondary and studio schools (map produced August 2015)



Appendix 7

NHDC email to HCC re. Education Need Paper

20 August 2015

From: Chris Carter [<mailto:Chris.Carter@north-herts.gov.uk>]
Sent: 20 August 2015 16:04
To: Alice Carrington
Cc: Kate Ma; David Hill; Clare Skeels
Subject: RE: Stevenage Secondary Education Need

Hi Alice,

Thanks very much for sending this through. An interesting read which clearly sets out the HCC view about the need for additional secondary capacity in the future, even taking account of the former Collenswood site.

I suppose my immediate question in the light of the three conclusions that have been drawn at the end of the document is about site selection.

The document states that the former school relocation site at Great Ashby is where the new school should be provided. However that proposal, largely, went away in 2010 after the BSF funding was stopped. Since then, time has clearly moved on and the landowner has sought to promote this site to us for housing, and as you know it was included as such in our Preferred Options consultation at the start of this year.

Can you tell me what work HCC has done to arrive at the view that this is the location in this part of the town where a school should be located. Has there been a site sifting exercise which has discounted other possible locations?

Thanks

Chris

Chris Carter
Senior Planning Officer

Direct Dial 01462 474477

North Hertfordshire District Council
Council Offices
Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

[Follow us on Twitter](#)
[Like us on Facebook](#)
www.north-herts.gov.uk

Appendix 8

HCC email to NHDC re. Education Need Paper

8 September 2015

From: Ailsa Davis [<mailto:Ailsa.Davis@hertfordshire.gov.uk>]
Sent: 08 September 2015 09:37
To: Chris Carter
Cc: Alice Carrington; Kate Ma; Dick Bowler
Subject: Stevenage Secondary Education Need

Chris,

Further to your email to Alice on the 20 August, I can advise Childrens' Services have passed this onto Development Services to provide you with a response.

I can advise that the Great Ashby site selection was founded on two principles under the BSF programme:

- 1) That there was an 8FE cohort of primary pupils living in the St Nicholas/Great Ashby area who would be 'exported' in whole from their neighbourhood to other parts of Stevenage to obtain secondary education and;
- 2) That there was a forecast deficit of secondary places across the whole Greater Stevenage area.

Hence, the Great Ashby site was ideally suited strategically, and the only suitable/available/deliverable site in their neighbourhood. As part of an assessment of potential alternative sites within the BSF project, sites across Stevenage were considered on a sequential basis with urban brownfield sites considered first, urban Greenfield sites second, and Green Belt sites third. The scope of search was limited to areas in north-east Stevenage for sites with a land area of at least 10 hectares (the minimum requirement for an 8FE school). Five option sites were identified. These are identified as Sites (A) Land at Canterbury Way ; (B) St Nicholas Park; (C) Land at Weston Road; (D) Land north east of Great Ashby; and (E) Land north and south of Nine Acre Spring. The five potential sites are shown on the attached plan. All sites were ruled out for various reasons, which can be seen in more detail on pages 30-31 of the planning application committee report here:

<http://www.hertsdirect.org/statweb/meetingsnov04toapr13/Development%20Control%20Committee/20100119/documents.html>

The Secondary Education Need paper sent to you on 19 August 2015 demonstrates that there is a continued need for a new secondary school to the north of Stevenage. The planning merits and circumstances surrounding the alternative sites outlined above have not changed. Therefore, the site at Great Ashby remains the only suitable/available/deliverable option.

I hope this provides you with the necessary background justification you were seeking, however if you have any other questions do not hesitate to come back to me.

Kind regards

Ailsa Davis
Senior Planning Officer, Development Services
Hertfordshire Property
Postal Point CHO313
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN
Tel: 01992 588275 **Comnet/Internal:** 28275
Working days: Tuesday, Wednesday and Thursday

Appendix 9

Email correspondence between HCC and NHDC

February to March 2016

From: Nigel Smith [<mailto:Nigel.Smith@north-herts.gov.uk>]
Sent: 11 February 2016 14:27
To: Ailsa Davis
Cc: David Hill; Simon Ellis; Clare Skeels
Subject: Education provision in North Herts / Local Plan

Hi Ailsa,

Good to meet you this morning and put a face to the name. Following up, I said I would drop you a line regarding the outstanding issues and concerns we have regarding education provision and our emerging Local Plan. As mentioned, we anticipate that the allocation (or otherwise) of sites through the plan are likely to be subject to particular scrutiny and we will need to satisfy all the relevant tests at examination.

Broadly speaking, the issues fall into three interrelated categories which are set out below. I'd be grateful if you could give these consideration. We will need to develop a position in consultation with one another over the next few months. However, if you have any initial thoughts or concerns, please get in touch.

I've deliberately left East of Luton of this list as, with the planning applications already in / anticipated, this is already a ship that is sailing its own course.

As mentioned, we are facing a particularly tight turnaround to meet the milestones set out in our recently adopted Local Development Scheme. We are broadly working to the following timetable:

- March – Finalise analysis of new sites promoted since the 'Preferred Options' consultation
- April – Identification of a 'preferred development scenario' for testing
- May / June – Testing implications of preferred development scenario with key service providers
- July – Approval of draft Local Plan by NHDC
- August to October – Consultation on draft Local Plan

I appreciate that there will be some substantial work associated with the below. However, a number of these issues have been around for some time now and we are increasingly under pressure to progress our Local Plan. I hope we can work co-operatively with each other to work through these matters and develop a solution for North Hertfordshire.

Issue 1: Justification of 1FE:500 homes ratio for additional provision

We have concerns around the overall justification for additional education requests and the evidence behind it.

With particular regard to the existing evidence behind the 1:500 ratio:

- It appears to have been generated from a relatively small county-wide survey;
- That survey was conducted some time ago and does not appear to have been subject to on-going monitoring; while
- A large amount of the requirement is derived from a 'statistical adjustment' from the survey average.

Although I appreciate the need for prudence in advance planning, the implications of setting requirements at (for example) 1:600, 1:700...etc needs to be understood. This could be the difference between additional schools, or the expansion of existing premises, being required or not. There needs to be an acceptable balance between the level of risk to which HCC are exposed and the impacts on development in terms of site yields, financial viability etc.

Linked to this is the fact that all additional future demand is effectively calculated on the basis it will happen simultaneously. There needs to be further consideration of how demand is profiled over time, how changes in living patterns (declining household sizes etc.) may change demand from within the existing stock etc.

As a high-level example, applying the 1:500 ratio to our anticipated housing target figure of 14,400 homes for North Herts would suggest a total 28.8FE of additional provision over the period 2011-2031. This equates to around ~6,000 additional places at primary school level (28.8 x 30 [class size] x 7 [reception to Y6]). By way of contrast, the latest Government population projections ~ which broadly align

with our proposed housing numbers ~ only anticipate a maximum increase of ~2,500 primary-aged children over the plan period.

Justification for the selection of the GA2 site at Great Ashby

Should the above still lead to an identified requirement for additional provision, we require further evidence on the site-selection process which has led to the identification of this site as the preferred location for additional secondary school provision for the Stevenage School Planning area. We are obliged to consider 'reasonable alternatives' before settling on a final strategy.

As well as looking at alternate locations in / immediately around Stevenage, these alternatives may include some more 'out of the box' options – such as the concept of modest 'all through' provision at Knebworth mentioned this morning (see below), thereby relieving pressure / releasing capacity elsewhere.

Settlement-wide solutions

Finally, we need to come to a series of solutions that work at settlement / school planning area level in consultation with yourselves and relevant landowners and promoters.

I'm aware that HCC hold a number of reserve sites that may could provide additional capacity in the education system. Presumably there is also some scope for the expansion of existing schools – either from within existing landholdings or with the acquisition of adjoining land.

As per above, the 'missing link' in the land to the east of Knebworth has now been promoted to us and we would be interested in exploring whether there is scope for a more comprehensive / holistic approach here that could realise some wider benefits – notably the concept of secondary school provision, either as an 'all-through' school linked to the existing Primary School or as a standalone proposition.

Similarly we have had, for example, additional sites promoted at Barkway and Codicote where the relocation and expansion (respectively) of existing schools could facilitate a comprehensive solution.

This process will need to be replicated across other towns and villages.

The other end of this equation is that, utilising some of these reserve sites could release some existing school premises for redevelopment over the plan period. On the presumption that HCC would seek to maximise value of these assets, any such sites should be promoted to NHDC for potential allocation / redevelopment asap, although I appreciate there may be a degree of circular logic here!

I currently envisage / suggest that we aim to set up a series of sessions in the second half of March or early April where we can work through these on an area-by-area basis to inform the 'preferred development scenario' identified above. This will ensure there aren't any unwanted surprises when we reach the testing stage.

Apologies for the length of the email, but I think it is helpful to be clear as to the additional work we consider is required. Feel free to forward this on within your organisation to those who may need to be involved.

Thanks
Nigel

Nigel Smith
Principal Strategic Planning Officer

Direct Dial: 01462 474847
North Hertfordshire District Council
Council Offices, Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

From: Ailsa Davis [mailto:Ailsa.Davis@hertfordshire.gov.uk]
Sent: 11 February 2016 15:59
To: Nigel Smith
Cc: David Hill; Simon Ellis; Clare Skeels
Subject: Education provision in North Herts / Local Plan

Hi Nigel

Thank you for your email, which is helpful in terms of looking ahead at what needs to be done. I can advise I will be commissioning site search work to inform issue 2, which will include NE Knebworth area we discussed this morning. I am happy to work with you on issue 3.

In terms of issue 1 (child yield), I have set up an internal meeting with the relevant officers in mid-March (earliest I could get everybody in the same room) to discuss this and will come back to you.

Regards

Ailsa Davis
Senior Planning Officer, Development Services
Hertfordshire Property
Postal Point CHO313
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN
Tel: 01992 588275 **Comnet/Internal:** 28275
Working days: Tuesday, Wednesday and Thursday

From: Nigel Smith
Sent: 24 February 2016 13:32
To: 'Ailsa Davis'
Subject: RE: Education provision in North Herts / Local Plan

Ailsa,

Please see attached trajectory as requested.

Regards
Nigel

Nigel Smith
Principal Strategic Planning Officer

Direct Dial: 01462 474847
North Hertfordshire District Council
Council Offices, Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

[Follow us on Twitter](#)
[Like us on Facebook](#)
www.north-herts.gov.uk

From: Ailsa Davis [<mailto:Ailsa.Davis@hertfordshire.gov.uk>]
Sent: 23 February 2016 11:28
To: Nigel Smith
Subject: RE: Education provision in North Herts / Local Plan

Hi Nigel

If you could re-provide it that would be very helpful. I understand that numbers/sites will change.

Thanks

Ailsa

From: Nigel Smith [<mailto:Nigel.Smith@north-herts.gov.uk>]
Sent: 23 February 2016 10:58
To: Ailsa Davis
Subject: RE: Education provision in North Herts / Local Plan

Hi Ailsa,

Sorry for the delayed reply – half term got in the way. As per original email below, we are currently working towards having a preferred site list by mid-April that we can share with you. At present, I don't have a 'new' trajectory beyond anything Richard Kelly / Chris Carter may have previously provided in relation to our last consultation.

I can (re-)provide this if needed on the understanding that the numbers and some sites will be changed / added in the Spring.

Thanks
Nigel

Nigel Smith
Principal Strategic Planning Officer

Direct Dial: 01462 474847
North Hertfordshire District Council
Council Offices, Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

[Follow us on Twitter](#)
[Like us on Facebook](#)
www.north-herts.gov.uk

From: Ailsa Davis [<mailto:Ailsa.Davis@hertfordshire.gov.uk>]
Sent: 16 February 2016 10:35
To: Nigel Smith
Cc: David Hill; Clare Skeels
Subject: Education provision in North Herts / Local Plan

Nigel

Would it be possible to forward me your emerging LP housing trajectory? It will be treated as confidential. It would be useful to see it to help with our discussions around the child yield calculation.

Many thanks

Ailsa Davis
Senior Planning Officer, Development Services
Hertfordshire Property
Postal Point CHO313
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN
Tel: 01992 588275 **Comnet/Internal:** 28275
Working days: Tuesday, Wednesday and Thursday

Current GB	New ref (sites in draft Local Plan)	Settlement	Housing market area																		
				2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	Total
yes	CD1	Codicote	W					24	25	24										73	
yes	CD2	Codicote	W								29	29								58	
yes	CD3	Codicote	W				24	24												48	
			Total	26	330	469	965	1083	1085	1203	1215	831	774	772	597	500	600	600	622	561	12233

Totals by housing market area:

S	26	184	292	733	798	779	800	800	584	574	550	525	450	500	450	412	350
C	0	131	162	145	121	113	161	119	18	0	22	22	0	0	0	10	11
W	0	0	0	24	48	25	24	29	29	0	0	0	0	0	0	0	0
A	0	15	15	13	0	0	0	0	0	0	0	0	0	0	0	0	0
L	0	0	0	50	116	150	200	250	200	200	200	50	50	100	150	200	200

S = Stevenage and A1 corridor; C = Cambridge; W = Welwyn Garden City; A = St Albans; and L = Luton.

From: Nigel Smith
Sent: 02 March 2016 13:54
To: 'Bob Chapman'
Cc: David Hill; Dick Bowler; Roger Arbon; Ailsa Davis; David Hill
Subject: RE: North Herts Local Plan - Potential housing sites on HCC land

Hi Bob,

From the information I have...

Sites included in the Preferred Options consultation

- Land off Clothall Road, Baldock (Preferred Options site ref BA2)
- Land east of Clothall Common, Baldock (BA3)
- Land south of Clothall Common, Baldock (BA4)
- Former Lannock School, Letchworth (LG9)
- Land north of Former Norton School, Letchworth (LG4)
- Former Norton School Playing Field, Croft Lane, Letchworth (LG10)
- Land north of Lindsay Close, Royston (RY4)

New sites promoted in response to Preferred Options consultation

- Freeman House, Radburn Way, Letchworth
- Land at Bedford Road, Ickleford

Regards
Nigel

Nigel Smith
Principal Strategic Planning Officer

Direct Dial: 01462 474847
North Hertfordshire District Council
Council Offices, Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

[Follow us on Twitter](#)
[Like us on Facebook](#)
www.north-herts.gov.uk

From: Bob Chapman [<mailto:Bob.Chapman@hertfordshire.gov.uk>]
Sent: 02 March 2016 12:40
To: Nigel Smith
Cc: David Hill; Dick Bowler; Roger Arbon; Ailsa Davis
Subject: RE: North Herts Local Plan - Potential housing sites on HCC land

Hi Nigel

I'll get back to shortly on a suitable date. To save me time hunting around, have you've got a list of the sites to hand that you could let me have ?

Bob Chapman

Senior Planning Officer, Development Services Team,
Property
Postal point CHO 313
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN
Tel 01992 588116 **Comnet / Internal:**28116
Bob.chapman@hertfordshire.gov.uk

From: Nigel Smith [<mailto:Nigel.Smith@north-herts.gov.uk>]
Sent: 02 March 2016 12:09
To: Bob Chapman
Cc: David Hill
Subject: North Herts Local Plan - Potential housing sites on HCC land

Hi Bob,

As you'll be aware, we're currently working towards the Pre-submission draft of our Local Plan.

Obviously, North of Baldock is progressing under its own steam, but there are a number of other potential residential sites that have been promoted by HCC – some of which were included in the Preferred Options consultation and others which were subsequently promoted.

Could we arrange a meeting to go through these and identify any outstanding issues, potential timescales for disposal and development etc.? It would be best to hold it here to allow relevant officers to dip in and out depending on the site / area. A Monday or a Friday would be best.

The following dates are possible. Please could you let me know if any of these are suitable for you:

- Monday 14 March – 11am
- Monday 21 March – 11am or 2pm
- Friday 1 April – 11am or 2pm

Regards
Nigel

Nigel Smith
Principal Strategic Planning Officer

Direct Dial: 01462 474847
North Hertfordshire District Council
Council Offices, Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

[Follow us on Twitter](#)
[Like us on Facebook](#)
www.north-herts.gov.uk

From: Ailsa Davis [mailto:Ailsa.Davis@hertfordshire.gov.uk]
Sent: 22 March 2016 15:36
To: Nigel Smith
Cc: Jacqueline Nixon; Sarah McLaughlin; Andrea Gilmour
Subject: Education provision in North Herts / Local Plan

Nigel

Further to your email of 11 Feb (copied below), we have now had an internal meeting to discuss the points you raise regarding child yield and the 1FE:500 homes ratio. Please treat this email as a holding response pending the issue of further information/evidence to you relating to an update of the HCC Property s106 toolkit model incorporating 2011 census data, which endorses the peak yield of 1FE per 500 dwellings.

More specifically, in relation to your comments below:

- Work is underway to monitor the original piece of research (county wide survey) in terms of reviewing completed developments to establish whether the 1FE:500 ratio is borne out in reality;
- As stated above, an update of the HCC Property s106 toolkit and Childrens' Services forecasting models has been undertaken to incorporate 2011 census data and is currently being written up to share;
- Can you advise what is the source of the 'latest Government population projections' you refer to? Is it the SNPP 2012 or Interim 2011?
- Site search work for a new secondary school site to serve Stevenage and North Herts has been commissioned and is due to be completed by the end of June. The results of this will be shared with you and will be submitted with the HCC Property representations to your next LP consultation.

As soon as the above information is available to share, I will forward it to you.

Regards

Ailsa Davis
Senior Planning Officer, Development Services
Hertfordshire Property
Postal Point CHO313
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN
Tel: 01992 588275 **Comnet/Internal:** 28275
Working days: Tuesday, Wednesday and Thursday

From: Nigel Smith

Sent: 24 March 2016 09:56

To: 'Ailsa Davis'

Cc: Jacqueline Nixon; Sarah McLaughlin; Andrea Gilmour; David Hill; Simon Ellis; Ian Fullstone; Louise Symes

Subject: RE: Education provision in North Herts / Local Plan

Ailsa,

Thanks for the update. Please keep us posted as you progress and of any emerging findings in terms of both pupil yields and sites. I am concerned about the timing of the site search work as it would probably arrive too late to incorporate any findings into the Publication version of the plan (in terms of Sustainability Appraisal, reporting deadlines etc.) as we are committed to reporting this to our Council in July but we are where we are.

Yes, the projections referred to are the 2012-SNPP / Household Projections.

Regards

Nigel

Nigel Smith

Principal Strategic Planning Officer

Direct Dial: 01462 474847
North Hertfordshire District Council
Council Offices, Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

[Follow us on Twitter](#)

[Like us on Facebook](#)

www.north-herts.gov.uk

Appendix 10

HCC email to NHDC re. Education Need Paper

8 September 2015

From: Nigel Smith
Sent: 18 April 2016 12:27
To: 'Ailsa Davis'
Cc: David Hill; Simon Ellis; Louise Symes; Andrea Gilmour; Jacqueline Nixon; Sarah McLaughlin
Subject: RE: Education provision in North Herts / Local Plan

Ailsa,

Thanks for sending the letter and explanation through. HCC's intention to continue relying on the 1:500 ratio in response to Local Plans is noted.

On a related note, we are hoping to obtain approval for our updated list of preferred local plan housing sites this week. Once this has been finalised, we will send through to HCC (and other relevant bodies) for informal / confidential comment to inform our Infrastructure Delivery Plan and publication version Local Plan which is due to go to Council in July. If you could be aware that it is coming as we are going to have to give all parties a fairly rigid window (probably 4-6 weeks) in which to respond.

Regards
Nigel

Nigel Smith
Principal Strategic Planning Officer

Direct Dial: 01462 474847
North Hertfordshire District Council
Council Offices, Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

[Follow us on Twitter](#)
[Like us on Facebook](#)
www.north-herts.gov.uk

Appendix 11

HCC letter to NHDC

12 May 2016

**Resources
Property**



Louise Symes
Planning Policy Manager
North Hertfordshire District Council
Gernon Road
Letchworth Garden City
SG6 3JF

HERTFORDSHIRE PROPERTY
Hertfordshire County Council
County Hall
Hertford SG13 8DE

Telephone 01992 588275
Minicom 01992 556611
E.Mail: ailsa.davis@hertfordshire.gov.uk
Contact: Ailsa Davis

Date 12 May 2016

Dear Louise

SECONDARY SCHOOL SITE SEARCH

To support the emerging local plan in North Herts, the County Council are undertaking a secondary school site search within and around the edge of Stevenage.

The need for the site search has been identified as a consequence of the rising demand from the existing population and the requirement for additional school places from the proposed housing to the north of Stevenage within the North Herts emerging Local Plan and to the east of Stevenage, within the East Herts emerging Local Plan.

This work is being undertaken in two stages.

First, Childrens' Services and Property have undertaken assessments of the existing secondary schools in Stevenage to determine the expansion capacity of each of these sites. This work has concluded that there are insufficient spaces within existing schools to meet the demand arising from the proposed housing within Stevenage and to the north and east of Stevenage, within North Herts and East Herts. This includes the 5FE of future secondary provision at Barnwell East allocated within the emerging Stevenage Local Plan.

Second, consultants (Vincent and Goring) have been appointed to undertake a site search to identify any potential secondary school sites within Stevenage and on the edge of Stevenage within North Herts and East Herts.

The methodology that is being employed is summarised below:



Using the site search criteria of a minimum 4ha building zone and a minimum overall site area of 12 to 15ha, potential new sites are being considered in accordance with the following sequential approach:

- Urban brownfield sites
- Urban greenfield sites
- Greenfield sites on the edge of urban areas

SITE SEARCH

- Define and map a study area to include existing planning and environmental constraints.
- Identify a 'long list' of sites meeting basic site requirements to provide 6FE capacity.
- Using a proforma undertake an initial analysis and sieve of the long list of potential sites and creation of a 'short list' of sites.
- For each potential school site produce a site identification plan and aerial photograph
- Undertake a site appraisal of up to 5 shortlisted sites (from public viewpoints) to be agreed with the client.
- For each of the 5 shortlisted sites set out the further technical and environmental investigations that would be required to determine the deliverability of each site.
- For each of the 5 shortlisted sites undertake a highways appraisal to examine the potential vehicular and pedestrian access points, access to existing public transport and the potential highway impact of a 6FE secondary school on the local highway network.

REPORT

Prepare report setting out methodology, site evaluation and overall conclusions (including a site recommendation(s)) together with site plans, aerial photographs, development principles plans and proformas for each site.

This work is due to be completed by 30 June 2016 and the results will be shared with you.

Yours sincerely

Ailsa Davis

**Ailsa Davis
Senior Planning Officer**

Appendix 12

Meeting between NHDC and HCC

24 May 2016

From: Nigel Smith [<mailto:Nigel.Smith@north-herts.gov.uk>]
Sent: 24 May 2016 16:17
To: Ailsa Davis; Andrea Gilmour; Sarah McLaughlin
Subject: North Herts Local Plan - site testing list

Hi Alisa (and all),

Thanks for coming in today to discuss HCC sites and education issues. As mentioned at the meeting, my apologies that you haven't received the site testing list for our local plan. My understanding was that you should have had this some time ago.

We have developed a 'preferred scenario' of housing sites to inform the next iteration of our local plan and associated infrastructure delivery plan (IDP), which is attached. It covers the whole period from 2011-2031 for completeness but obviously any completions / permissions should have already been taken into account so should be excluded. This site list is confidential and I'd be grateful if you could treat it as such – fine to send on to others in your organisation that need to see it with this caveat.

I have also identified some specific issues where it would be useful to have some further guidance from HCC on education matters. As discussed at the meeting, we have a tentative understanding with two landowners at north-east Stevenage and east of Knebworth that any allocation on their land will require further exploration of education solutions – with the possibility of some modest, all-through / secondary provision. Both sites remain subject to the results of the other infrastructure testing currently being carried out, notably on highways.

Some homes are currently assigned to an 'unspecified' location – these are the small scale windfalls and also an allowance for sites we anticipate will be identified in the next review of the plan post-2026. The third attachment sets out how the IDP is generally dealing with this issue. You may wish to use the splits set out in the attachment for consistency but, equally, I am mindful that the windfalls will end up being more widely spread (i.e. some going to the villages) whilst the 500 homes to 'broad locations' may end up being in another location altogether (West of Stevenage, new settlement etc) so please give some consideration as to how you wish to deal with these.

Our original timetable was to set a deadline of June 3rd for responses. If you can still meet that then great(!) but, given the delay, could I ask that you let us know of any major issues by 10th June (along with as much additional information as you can reasonably provide in that timescale) and a final response by Friday 17th June.

Thanks in advance for your time and apologies again.

Nigel

Nigel Smith
Principal Strategic Planning Officer
Direct Dial: 01462 474847
North Hertfordshire District Council
Council Offices, Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

[Follow us on Twitter](#)
[Like us on Facebook](#)
www.north-herts.gov.uk

Appendix 13

Email exchange between HCC and NHDC

17 July 2016 – 22 July 2016

From: Sarah McLaughlin [mailto:Sarah.McLaughlin@hertfordshire.gov.uk]
Sent: 22 July 2016 14:58
To: Nigel Smith; Andrea Gilmour; Jacqueline Nixon
Cc: Alexandra Stevens
Subject: FW: Education provision in North Herts / Local Plan

Nigel,

We've had a brief discussion regarding your request for a report/analysis of information which supports the work done on the 2011 Census data. As I'm leave next week I thought it might be prudent to explain the current position as soon as possible.

We were not anticipating providing any further information at this stage, so it would be helpful if you could provide further clarification on information which may be required by your team, deadlines, intended use etc. We can then consider how best to meet your request. The HCC demographer is signed off until the end of July so this may delay a response. The work completed to date has been supporting our update to the HCC Toolkit which is not due to be available until this autumn.

As you are aware, Andrea is covering the Local Plan work in Ailsa's absence but is on leave today.

Kind regards,

Sarah

From: Sarah McLaughlin
Sent: 15 July 2016 15:33
To: 'Nigel Smith'
Cc: Andrea Gilmour
Subject: Education provision in North Herts / Local Plan

Hi Nigel,

Further to a meeting this morning, I understand that you are still awaiting some further information from HCC regarding the 1:500 ratio. I attach earlier communications for reference.

Happy to discuss if that would be easier?

Thanks,

Sarah

Sarah McLaughlin
Principal Infrastructure Officer
Development Services
Property, Resources Directorate
Postal point CHO 313
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN
Tel 01992 588110 **Comnet / Internal:** 28110 **Mobile** 07812 323488

Appendix 14

NHDC email to HCC

23 January 2017

From: Nigel Smith
Sent: 23 January 2017 16:14
To: 'Andrea Gilmour'
Subject: RE: HCC Property (DS) reps on behalf of HCC services

Andrea,

Thank-you for the representations you submitted to our Local Plan consultation last year on behalf of HCC services. It would be helpful for us to meet to discuss these and consider a way forward in advance of the plan being submitted for examination.

Notwithstanding the content of your objections, we retain significant concerns over HCC's method for calculation of future requirements, especially when compared to the Government's population projections that we are required to use as the 'starting point' for our Local Plans. The detailed site- / settlement-level requirements you have identified in your representations flow from these starting assumptions.

NHDC and HCC are both scheduled to appear at the examination of Stevenage's local plan next month when the Inspector has asked to discuss the 'soundness' of the evidence underpinning education requirements. Our statement to that session is attached for your information so you can see our position set out.

In advance of that hearing, the best date for a meeting from our end would be the afternoon of Monday 6 February. Alternatively (in descending order of preference) Tuesday 7 Feb (pm), Thursday 2 Feb (am) and Friday 3 February (pm) would be possible.

Please could you let me know if you and colleagues are able to make any of the above – if you could let me know who would be best to attend from your end?

We will arrange a meeting to discuss the representations you submitted as landowner in support of the plan separately in due course.

Thanks
Nigel

Nigel Smith
Principal Strategic Planning Officer

Direct Dial: 01462 474847
North Hertfordshire District Council
Council Offices, Gernon Road
Letchworth Garden City
Hertfordshire
SG6 3JF

[Follow us on Twitter](#)
[Like us on Facebook](#)
www.north-herts.gov.uk

Appendix 15

Meeting between HCC and NHDC re. education
provision

2 February 2017

From: Andrea Gilmour [mailto:Andrea.Gilmour@hertfordshire.gov.uk]
Sent: 02 February 2017 16:30
To: Nigel Smith
Cc: Jacqueline Nixon; Tony Bennetts
Subject: RE: HCC Property (DS) reps on behalf of HCC services

Nigel

I am attaching the response to your matters statement that has been sent to the Programme Officer for the Stevenage EiP.

Of the dates you provided the only time that Tony Bennetts (County Demographer), Jacqueline Nixon and I are available is 1 to 2 pm on 7 February at County Hall. Please could you confirm that you are able to attend?

Thank you.

Andrea

Andrea Gilmour
Principal Planning Officer, Development Services
Property, Resources
Postal Point CHO313
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN
Tel: 01992 556477 **Comnet/Internal:** 26477

Appendix 16

Meeting between HCC and NHDC re. education
provision

9 March 2017

From: Ian Fullstone [<mailto:Ian.Fullstone@north-herts.gov.uk>]
Sent: 10 March 2017 09:23
To: Jacqueline Nixon
Subject: NHDC Education Study

Dear Jacqueline,

Thank you for your time yesterday at what I thought was a very productive and useful meeting.

As promised please find attached a copy of the brief for the education study we have commissioned. As agreed, Regeneris will use you as the first point of contact at HCC.

I have spoken to Policy colleagues here and they support the approach we discussed yesterday with regard a Statement of Common Ground. Hopefully you will be able to let me know HCC's view shortly.

Best Regards
Ian

Appendix 17

HCC email to NHDC re. alternative school site

23 March 2017

From: Jacqueline Nixon
Sent: 23 March 2017 16:48
To: 'Ian Fullstone'
Subject: RE: NHDC Local Plan

Ian

Further to the letter below we have just had some initial site search work back from our consultants. It appears that we may have identified an alternative school site, although we are awaiting further details . Could Andrea Gilmour (Principal Planning Officer) and I come to talk to your team about the sites? We can both make 4th April am . Will you advise if that works for you, we are happy to come to your offices.

regards

Jacqueline Nixon

Head of Development Services
Property
Postal point CHO 313
Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN
Tel 01992 588104 **Comnet / Internal:** 28104

Appendix 18

HCC sends two transport assessments to NHDC

12 April 2017

-----Original Appointment-----

From: Andrea Gilmour [<mailto:Andrea.Gilmour@hertfordshire.gov.uk>]

Sent: 12 April 2017 08:25

To: Andrea Gilmour; 'Richard Javes'; Claire Sime; Pierce Jenny; Louise Symes; Kate Ma; Alice Carrington; Roger Flowerday; 'Liz Fitzgerald'; Nigel Smith

Cc: Jacqueline Nixon; 'S.Tiley@welhat.gov.uk'

Subject: Stevenage Secondary School Site Search Update

When: 24 April 2017 15:30-17:00 (UTC+00:00) Dublin, Edinburgh, Lisbon, London.

Where: Vincent and Goring Sterling Court Norton Road Stevenage SG1 2JY

****Disclaimer****

The information in this message should be regarded as confidential and is intended for the addressee only unless explicitly stated. If you have received this message in error it must be deleted and the sender notified. The views expressed in this message are personal and not necessarily those of Hertfordshire County Council unless explicitly stated. Please be aware that emails sent to or received from Hertfordshire County Council may be intercepted and read by the council. Interception will only occur to ensure compliance with council policies or procedures or regulatory obligations, to prevent or deter crime, or for the purposes of essential maintenance or support of the email system.

From: Andrea Gilmour [<mailto:Andrea.Gilmour@hertfordshire.gov.uk>]

Sent: 12 April 2017 08:34

To: 'Richard Javes'; 'Claire Sime'; 'Pierce Jenny'; Louise Symes; Kate Ma; Alice Carrington; Roger Flowerday; 'Liz Fitzgerald'

Cc: Jacqueline Nixon; sue tiley

Subject: Stevenage Secondary School Site Search Update

Dear All

In advance of our meeting on 24 April I am attaching the Transport Assessments undertaken for two additional sites to the North of Stevenage along with a summary note of the findings.

If you have any questions please let me know.

Thanks

Andrea

Andrea Gilmour

Principal Planning Officer, Development Services

Property, Resources

Postal Point CHO313

Hertfordshire County Council, County Hall, Pegs Lane, Hertford, SG13 8DN

Tel: 01992 556477 **Comnet/Internal:** 26477

****Disclaimer****

The information in this message should be regarded as confidential and is intended for the addressee only unless explicitly stated. If you have received this message in error it must be deleted and the sender notified. The views expressed in this message are personal and not necessarily those of Hertfordshire County Council unless explicitly stated. Please be aware that emails sent to or received from Hertfordshire County Council may be intercepted and read by the council. Interception will only occur to ensure compliance with council policies or procedures or regulatory obligations, to prevent or deter crime, or for the purposes of essential maintenance or support of the email system.

Summary Note

Stevenage/North Hertfordshire Secondary School Site Search

Update Report

Introduction

HCC commissioned Vincent and Gorbing to undertake a comparative site search to identify a suitable secondary school site to meet and identified 8FE future requirement to the north of Stevenage. The report was completed in July 2016.

Following the completion of the report a meeting was held with Stevenage Borough Council, North Herts District Council, East Hertfordshire District Council and Welwyn Hatfield Borough Council on the 15th July to review the findings and discuss a way forward.

The report identified a single site to the north of Great Ashby as the preferred location to meet the identified educational need (GA2). This was discussed with all Council's and it was noted that the site had been promoted in the emerging Local Plan as a housing site with 4ha of land for educational use, to meet the needs of a primary school and secondary school.

Whilst the identified 4ha is not a sufficient area to meet the needs of a secondary school, let alone a secondary and primary school, a Transport Assessment has been undertaken by the landowner/promoter and it has been demonstrated that the access arrangements proposed for the site would not be able to cope with a combination of residential/primary and secondary provision. Such that a secondary school could not be located in this identified area proposed for allocation.

As a consequence of this outcome, the emerging plan was reviewed and alternative sites identified as potential locations for a secondary school. These sites comprised Land at Back Lane and Land South West of Claypits Woods.

Further Site Identification Work.

The direction of need was the target area for further consideration, that being to the north of Great Ashby.

Land South West of Claypits Woods was initially identified, due to its proximity adjacent to the preferred GA2 site. Simultaneously we were contacted by our land agents for the site identified as Land at Back Lane.

Given both sites location adjacent to proposed development sites and access to a road network, it was decided to pursue the potential for either of these sites being suitable for a secondary school site.

All landowners/agents associated with these sites were invited to meet with HCC, with a view to sharing the work that was being undertaken and ascertaining interest in the potential of releasing their land.

STERLING COURT NORTON ROAD STEVENAGE HERTS SG1 2JY
T: 01438 316331 F: 01438 722035 E-mail: architects@vincent-gorbing.co.uk planners@vincent-gorbing.co.uk
WWW.vincent-gorbing.co.uk

Summary Note

Phil Jones Associates were also commissioned to undertake Transport Assessments for both sites, to enable a comparison to be made in respect of highway capacity matters and connectivity.

Site A: Land at Back Lane.

We were approached by agents on behalf of the landowner with a view to considering Site A as a potential secondary school site. The landowner is promoting land to the north of this proposed site for circa 150 aspirational housing.

The site is located to the west of the Great Ashby Linear Park, to the north of site allocation NH8, which is open space associated with Forster Country, beyond which, towards North Road are two housing site allocations.

The site is considered to be well sited to meet the identified educational need and unlike sites towards the east would also be well placed to serve the proposed housing site allocations to the west.

The potential accessibility of the site has been considered as part of the Transport Assessment. At present the site has limited access potential, being linked to Back Lane only to the north, which is a narrow country lane unsuitable for the extent of traffic associated with a 6-8FE secondary school

The site is however well placed in respect of proposed growth to the North of Stevenage, such that connections to the west can be achieved via the new housing developments if appropriately masterplanned.

To the east the site is situated adjacent to the Linear Park, this provides access opportunities into Great Ashby, with a new road created through the end of the park area and joining at Great Ashby Way /Orwell Avenue. This access arrangement replicates that previously approved for the GA2 site, when planning permission was obtained for a secondary school in that location, such that the principle can be deemed to be acceptable.

Having considered the cumulative impacts of both residential development and the addition of a school, the following highway enhancements would be required:

- Mitigation at the Great Ashby Way, east of Orwell Avenue;
- A controlled pedestrian crossing on Great Ashby Way, east of Orwell Avenue;
- High quality pedestrian/cycle routes from the site allocations west of the proposed school;
- Mitigation at the Great Ashby Way/Bray Drive roundabout.

In respect of other material planning considerations, the site is an open space, with some sporadic trees through the site and denser belts to the boundaries to the south. In general planning terms, the constraints associated with the development of this site are therefore primarily associated with the delivery of an appropriate access arrangement.

The site has been suggested to the County Council as a potential school site by the landowners' agent's, the site can therefore be deemed to be available. The delivery of appropriate access arrangements falls within land owned by both HCC and Stevenage Borough Council, such that there is no additional third party land ownership that would prevent the site from being delivered.

Summary Note

There are no foreseen planning constraints that would prevent the site from being developed in a sympathetic manner, addressing matters pertaining to character and appearance of the area, neighbour amenity and highway safety. Accordingly, it is considered that the site is deliverable.

Finally, in respect of sustainability, the site is located adjacent to both the existing and proposed residential areas, and as set out within the Transport Assessment, would readily serve a wide catchment area, enabling non-car modes of transport to be a primary mode of transport. The site is therefore considered to be sustainable.

Site B: Land South West of Claypit Woods

The land is in private ownership and is not currently available for development. The landowner has been contacted and verbally advised that they were not willing to release their site for development. It is therefore assumed that the development of this site could only occur following the compulsory purchase of the site.

The site is located to the north of Great Ashby, to the north of site allocation GA2 and GA1 to the south west and is currently agricultural land. Access to the site is via Back Lane to its southern boundary.

The site is considered to be well sited to meet the identified educational need within Great Ashby and demand from some of the proposed housing allocations to the north of Great Ashby generally.

The potential accessibility of the site has been considered as part of the Transport Assessment. At present the site has limited access potential, being linked to Back Lane only to the south, which is a narrow country lane unsuitable for the extent of traffic associated with a 6-8FE secondary school

Due to the location of the site to the north of the area, the ability to provide suitable connections is restricted. Access could only be provided to the south, resulting in the need to widen Back Lane and provide connections through to GA1 and GA2. These connections would be over additional third party and could not be provided solely within Council land.

The ability to acquire this land is currently unknown and development of this nature will significantly change the character and appearance of the area, particularly Back Lane.

Having considered the cumulative impacts of both residential development and the addition of a school, the following highway enhancements would be required:

- A controlled pedestrian crossing on Great Ashby Way, east of Orwell Avenue;
- Additional pedestrian/cycle routes to the south and through site allocations;
- Parking restrictions on estate roads.

In respect of other material planning considerations, the site is an agricultural field, with some tree belts to the boundaries of the land. In general planning terms, the constraints associated with the development of this site are therefore primarily associated with the delivery of an appropriate access arrangement.

Summary Note

The site is not currently available and the landowner has stated that they are not interested in releasing the site. Furthermore, to deliver the access improvements required to gain access into the site, further third party land is required. We have endeavoured to contact all third parties, however a number have not replied. We cannot therefore state that the site is deliverable.

There are no foreseen planning constraints that would prevent the site from being developed in a sympathetic manner, addressing matters pertaining to character and appearance of the area and neighbour amenity, however, the ability to deliver the site access arrangements may be more challenging. Accordingly, it is considered that the site is not deliverable.

Finally, in respect of sustainability, the site is located adjacent to both the existing and proposed residential areas, and as set out within the Transport Assessment, would readily serve a wide catchment area, however, access arrangements are limited and the site is slightly out on a limb to the north of the proposed developed area. Accordingly, it is not considered that this site is the most sustainable location for this development.

Conclusions

The area has been considered thoroughly in respect of trying to find a suitable site for development of a much needed school, especially when having regard to the additional housing growth adjacent.

Following the exclusion of the preferred site at GA2, consideration has been given to two alternative locations also to the north of Great Ashby. Following the completion of a Transport Assessment on both sites, it is clear that Site A, Land at Back Lane, is more accessible and will provide access to secondary education for all of the proposed housing sites to the north of Stevenage, as opposed to those located towards the east. This site would also offer the ability to provide a more joined up holistic development to the north of Stevenage, than the individual developments that would result without this site to the centre of the areas.

Both sites are similarly constrained in respect of material planning issues, but Site B does not benefit from good highways connections or pedestrian links, in addition the land is not currently available for development.

Overall, Site A is better located and can be deemed to be available, deliverable and sustainable. Whilst not in the preferred location for the direction of need, as set out in the Site Search Report, it is considered to be the most desirable sites available and should be promoted via the emerging Local Plan process.

LF 27th March 2017

From: Louise Symes
Sent: 12 April 2017 13:36
To: 'Andrea Gilmour'
Cc: Ian Fullstone; Nigel Smith
Subject: RE: Stevenage Secondary School Site Search Update

Dear Andrea

Thank you for the information , both Nigel Smith and I will be attending the meeting.

Regards Louise